

LAYOUT NOTES:

1. ESTABLISH HORIZONTAL BASELINES AND OFFSET LINES PARALLEL AND PERPENDICULAR AS INDICATED FROM THE EXISTING CONTROL POINTS SET BY OWNER. VERTICAL CONTROL IS RELATIVE WITHIN THE WORKSITE. ESTABLISH SPECIFIC VERTICAL RELATIONSHIPS PRIOR TO STARTING WORK. ESTABLISH A MINIMUM OF TWO VERTICAL CONTROL POINTS AND MAINTAIN THEM THROUGHOUT THE PROJECT. THE BASELINES AND OFFSET LINES ARE TO BE ESTABLISHED AS SHOWN ON THE PLAN.
2. ALL CURVED LINES INDICATED ON THE LAYOUT SHALL BE CONTINUOUS AND WITHOUT DEVIATION. ABRUPT VERTICAL OR HORIZONTAL CHANGES ARE NOT ACCEPTABLE. STAKE CONCRETE FORMS ADEQUATELY TO PREVENT SUDDEN BENDS.
3. NOTIFY THE ENGINEER OF HORIZONTAL OR VERTICAL DISCREPANCIES IMMEDIATELY. DO NOT PROCEED WITH WORK WHICH MAY RESULT IN ACCUMULATED ERROR.
4. NOTIFY ENGINEER OF LAYOUT DISCREPANCIES WITH ELEMENTS TO REMAIN AND PROPOSED ELEMENTS. DO NOT PROCEED WITH WORK WHICH MAY RESULT IN ACCUMULATED ERROR.
5. STAKE OUT PAVING AND SITE FURNISHINGS PRIOR TO THE INSTALLATION OF THESE ITEMS. INSTALLATION MAY PROCEED AFTER SECURING APPROVAL FROM THE ENGINEER.

MATERIAL NOTES:

1. PAVERS TO BE: PAVESTONE UNI-ECOPAVERS - DARK GREY
2. PICNIC TABLES TO BE: FAIRWEATHER f-7 TABLE WITH 2 SEATS AT EACH TABLE, EMBEDDED, COLOR: BLACK


**>>>>CAUTION - CALL 811<<<<
UTILITY NOTIFICATION CENTER
BEFORE YOU DIG!
WWW.CALL811.COM**

ALSO CONTRACT WITH A COMMERCIAL UNDERGROUND UTILITIES LOCATOR SERVICE TO IDENTIFY BELOW-GROUND INFRASTRUCTURE THAT MAY NOT BE LOCATED BY CALL 811 BEFORE-YOU-DIG.

NO.	REVISION - AS BUILT	DATE
1		

REVIEWED: _____ DATE _____
PARK ENGINEER

All work done in accordance with the City of Seattle Standard Plans and Specifications in effect on the date shown above, and supplemented by Special Provisions.



STATE OF WASHINGTON
LICENSED
LANDSCAPE ARCHITECT


R. FRANK ROBINSON
LICENSE NO. 505
EXPIRES ON 06/26/2015



**SUMMIT SLOPE PARK
JOHN STREET ENHANCEMENT
SITE LAYOUT PLAN**

DESIGNED RFR	DATE MAY 2016
DRAWN RFR	SHEET 5 OF 8
CHECKED SH	
ORDINANCE NO. 123560	
CONTRACT NO. 1912	
SCALE 1"=10'	

DATE	MARK	NATURE	REVISIONS



REVIEWED BY SPU/WATER ENGINEERING	NAME OR INITIALS AND DATE	INITIALS AND DATE
DESIGNED	REVIEWED:
CHECKED	PROJECT MANAGER
REVIEWED BY SPU/DRAINAGE	DRAWN	REVISED AS-BUILT
.....	CHECKED
APPROVED BY SDOT STREET IMPROVEMENT PERMITTING	DESIGN REVIEW	
.....	



SCALE: H. V. INSPECTOR'S BOOK

**200 SUMMIT AVE E
JOHN STREET ENHANCEMENT
SITE LAYOUT PLAN**

SDOT PROJECT NO.
VAULT PLAN NO. 790-410
VAULT SERIAL NO. 36723
SHEET 5 OF 8