

## **Director's Rule**

Title		Number	Rev. no.	
Stormwater Facility Credit Calculator	DWW-260.2	2		
Responsibility	Supersedes	Pages		
People, Culture & Community Branch; Drainage and Wast	ewater Line of Business	N/A	2	
General Manager/CEO Signature (interim)	Approval Date	Effective Date		
/s/ Andrew Lee [e-signature on file]	November 29, 2021	November 29	, 2021	

### 1. PURPOSE

To improve the equity of drainage charges, Seattle Public Utilities (SPU) has developed a Stormwater Facility Credit Program. This program provides credits on drainage bills to customers who have installed approved stormwater management facilities that mitigate the impact on the City's drainage system of stormwater runoff from their property. Approved stormwater management facilities must meet applicable technical design requirements described in the City's Stormwater Code ("Stormwater Code") SMC 22.800.

The revised Stormwater Code became effective on July 1, 2021 per Ordinance 126336. The General Manager/CEO of SPU has established the 2021 Stormwater Facility Credit calculator ("2021 SFC Calculator") that reflects the updated performance goals of the City's Stormwater Code, as established per Ordinance 126336. The 2021 SFC Calculator applies to facilities built according to 2021 code requirements.

The General Manager/CEO has also maintained the three preceding calculators which reflect the performance goals of the prior City Stormwater Codes. The 2016 SFC Calculator ("2016 SFC Calculator") applies to facilities constructed according to 2016 code requirements. The 2009 SFC Calculator ("2009 SFC Calculator") applies to facilities constructed according to 2009 code requirements. The 2000 SFC Calculator ("2000 SFC Calculator") applies to facilities constructed according to 2000 code requirements.

## 2. RULE

SPU has developed a "credit calculator" that is the formula used to calculate the percentage credit for each eligible parcel that has applied for such a credit on its drainage bill. The output of the credit calculator is a percentage credit, which may not exceed a maximum percentage, as specified in SMC 21.33.040. Credits are rounded to the nearest whole percentage, with no credit offered to calculated credits that round to less than 1 percent. The credit is then applied as a percentage discount to the customer's annual drainage bill for the parcel.

This credit calculator assigns a uniform percentage credit for each type of approved stormwater management facility, based on a weighting of the stormwater performance goals the facility satisfies and that are applicable to the appropriate drainage discharge point for that parcel. The credit calculator then considers information specific to the parcel, which is entered into the calculator by SPU, such as the percentage of the parcel's impervious surface managed by the approved facility and the parcel's drainage rate category assignment.

The 2021, 2016, 2009 and 2000 SFC Calculators include "Rate Tier Multipliers" which reflect the percentage of the drainage bill associated with runoff from impervious surface, with such multipliers used in the calculation of the final stormwater facility credit applied to a parcel's drainage bill. The Rate Tier Multipliers vary by rate tier.

A list of all facilities that qualify as "approved stormwater management facilities" under this program is found in Table 1 (2000 SFC Calculator), Table 2 (2009 SFC Calculator), Table 3 (2016 SFC Calculator), Table 4 (2021 SFC Calculator) of Attachment A to this Director's Rule.

### 3. REFERENCES

- SMC 21.33.040, Stormwater Facility Credit Program
- SMC 22.800, Stormwater Code
- Ordinance 126336, amending Stormwater Code provisions

### 4. ATTACHMENTS

- Attachment A Table 1, Stormwater Facility Credit Program Credit Percentage Calculation: For facilities built according to 2000 and previous code requirements
- Attachment A -Table 2, Stormwater Facility Credit Program Credit Calculator: For facilities built according to 2009 code requirements
- Attachment A -Table 3, Stormwater Facility Credit Program Credit Calculator: For facilities built according to 2016 code requirements
- Attachment A -Table 4, Stormwater Facility Credit Program Credit Calculator: For facilities built according to 2021 code requirements

Effective: November 29, 2021

## Attachment A - Table 1. Stormwater Facility Credit Program Credit Percentage Calculation: For Facilities Built According to 2000 and Previous Code Requirements

	_			<del>_</del>						_	Rate Tier (3):	
					<u></u>	Pe	rcent Reduction b	y Performance Ta	rget		Overall Max:	50%
Site Impervious Managed	Basin Type	Design Standard	BMP Classification	Facility	Properties	TSS	Volume	2-yr Peak & Duration	25-yr Peak	Flow Credit Basis	Facility Credit (1)	Adjusted Facility Credit (2
iter Quality (WQ) : Typically not C	) - PGIS Area / Total Imp SO basins	erviousness			Weighting=	60%	40%	0%	0%			
0%	Separated System	6-month, 24-hour storm	Water Quality - Level 1		no infiltration	80%	0%	NA	NA	Media filter (evaluated)	24%	0%
0%	Separated System	6-month, 24-hour storm	Water Quality - Level 2	wetponds, bioswales (basic, wet, and continuous inflow), filter strips	some infiltration (storage)	80%	15%	NA	NA	Wetpond (modeled)	27%	0%
0%	Separated System	6-month, 24-hour storm	Water Quality - Level 3	sand filter, bioretention or pervious pavement without underdrain, bioretention with underdrain	relies entirely on infiltration	95%	98%	NA	NA	Bioret w/o underdrair (modeled)	48%	0%
	1) (Public Combined Ser equate pipe conveyance	wer/Capacity Constrained Basin) and/or ditching			Weighting=	0%	25%	40%	35%			
0%	Public Combined Sewer/Capacity Constrained Basins	2- and 25-year peak control	Detention - Level 1	vegetated roof (min. 4" soil depth)	no infiltration (some soil storage and evapotranspiration)	NA	30%	25%	20%	Professional Judgment	13%	0%
0%	Public Combined Sewer/Capacity Constrained Basins	2- and 25-year peak control	Detention - Level 2	cistern, vault, detention pipe or surface detention with impermeable liner	no infiltration	NA	0%	22%	63%	Vault (modeled)	16%	0%
0%	Public Combined Sewer/Capacity Constrained Basins	2- and 25-year peak control	Detention - Level 3	surface detention	minimal infiltration (some soil storage and evapotranspiration)	NA	5%	22%	81%	Pond (evaluated)	19%	0%
0%	Sewer/Capacity Constrained Basins Public Combined	2- and 25-year peak control	Detention - Level 4	infiltration trench, bioretention (cell or planter), or pervious pavement facility all with underdrain	some infiltration (storage)	NA	24%	79%	81%	Professional Judgment	33%	0%
0%	Sewer/Capacity Constrained Basins	2- and 25-year peak control	Detention - Level 5	infiltration trench, dry well, bioretention (cell or planter), or pervious pavement facility all without underdrain	relies entirely on infiltration	NA	98%	99%	81%	Infiltration Trench (modeled)	46%	0%
w Control 2 (FC2 Creeks and small	2) (Flow Critical Receivi	ng Water Basin)			Weighting=	15%	10%	35%	40%			
0%	Flow Critical Receiving Water Basin	2-, 25- and 100-year peak control	Detention+100yr - Level 1	vegetated roof (min. 4" soil depth)	no infiltration (some soil storage and evapotranspiration)	0%	30%	25%	20%	Professional Judgement	10%	0%
0%	Flow Critical Receiving Water Basin	2-, 25- and 100-year peak control	Detention+100yr - Level 2	cistern, vault, detention pipe or surface detention with impermeable liner	no infiltration	0%	0%	25%	76%	Vault (modeled)	20%	0%
0%	Flow Critical Receiving Water Basin	2-, 25- and 100-year peak control	Detention+100yr - Level 3	surface detention	minimal infiltration (some soil storage and evapotranspiration)	8%	6%	25%	81%	Pond (modeled)	22%	0%
0%	Flow Critical Receiving Water Basin	2-, 25- and 100-year peak control	Detention+100yr - Level 4	infiltration trench, bioretention (cell or planter), or pervious pavement facility all with underdrain	some infiltration (storage)	98%	29%	99%	81%	Professional Judgment	43%	0%
0%	Flow Critical Receiving Water Basin	2-, 25- and 100-year peak control	Detention+100yr - Level 5	infiltration trench, dry well, bioretention (cell or planter), or pervious pavement facility all without underdrain	relies entirely on infiltration	98%	98%	99%	81%	Infiltration Trench (modeled)	46%	0%
nwater Harvesti	ing Credit - % of Roof Ar	ea										
0%	All	Rainwater use - for Commercial Properties	NA	Tank with reuse	<u> -</u>	NA	NA	NA	NA	<u> </u>	10%	0%
										Total Adjusted Facil	ity Credit	0%

Final Parcel Credit Calculation	
Total Adjusted Facility Credit	0%
Rate Tier Multiplier (3)	0%
Final Parcel Credit (4)	0%

## Notes:

- 1) The facility credit is the scaled weighted average of the percent reductions by performance target.
- 2) The adjusted facility credit is the facility credit multiplied by the percentage of total impervious area managed by the applicable facility.
- 3) The rate tier multiplier is the percentage of the customer's bill attributable to impervious area run-off. Credit is only offered for run-off managed which originates on impervious surface.
- 4) The Final Parcel Credit is the rate tier multiplier multiplied by the sum of a property's adjusted facility credits (i.e., the "total adjusted facility credit"). The Final Parcel Credit is capped at 50%. The Final Parcel Credit is the credit percentage applied to the customer bill.

Rate Tier Multipliers		% Impervious or Parcel Area	Tier	Multiplier (see note 4)
General Service/Large Residential	Undeveloped-Regular	0-15%	G1	30%
	Undeveloped-Low Impact	0-15%	G1L	23%
	Light-Regular	16-35%	G2	63%
	Light-Low Impact	16-35%	G2L	62%
	Moderate-Regular	36-65%	G3	83%
	Moderate-Low Impact	36-65%	G3L	79%
	Heavy	66-85%	G4	93%
	Very Heavy	86-100%	G5	99%
Small Residential		<2,000 sq ft	R1a	85%
		2,000-2,999 sq ft	R1b	84%
		3,000-4,999 sq ft	R2	79%
		5,000-6,999 sq ft	R3	78%
		7,000-9,999 sq ft	R4	74%

Rate Tier:	٦										
						Douformones F	·aatara		Maximum Facility Credit	E00/	1
						Performance F	actors		racility Credit	50% Adjusted	
						2-yr Peak &			Facility Credit		t
% Impervious Surface Managed		WQ/FC Classification	Stormwater Facility Type	TSS	Volume	Duration	25-yr Peak	Flow Credit Basis	(1)	(2)	Notes
	at PGIS Area/Total Impervious (5) of the water quality design storm volume	or flow rate									
	g basic, enhanced, phosphorus, or oil trea		Weighting=	= 60%	40%	0%	0%				
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Traditional stormwater infrastructure		Media filter					I	I		Flow modeling not needed. Water quality performance
0%	(non-infiltrating facilities)	WQ- Level 1	Oil/water separator Wet vault	80%	0%	NA	NA	Media filter (evaluated)	24%	0%	based on Ecology's General Use Level Designation (GULD basic treatment (TSS removal) goal.
	Traditional stormwater infrastructure		Detention/wet pond Detention/stormwater wetland								Flow modeling not needed. Water quality performance based on basic treatment goal in the Stormwater
	(minimal evaporation)	WQ- Level 2	Bioswales (basic, wet, and continuous inflow)	80%	0%	NA	NA	Wetpond (modeled)	24%	0%	Management Manual for Western Washington (Ecology
0%			Filter strips Bioretention cell (without underdrain)		+			Bioret w/o underdrain			2005). Flow modeling not needed. Water quality performance
0%	Infiltration and reuse facilities	WQ- Level 3	Permeable pavement facility (without underdrain)	95%	91%	NA	NA	(modeled)	47%	0%	estimated based on professional judgment.
	en Stormwater Infrastructure to the Maxin		Only								
Design Standard: 91 percent Basin types: All	infiltration or 91 percent reduction for 1-y	ear peak flow	Waladata a	00/	500/	F00/	00/				
Basili types. All	11 - 60 - 6 - 7 - 70		Weighting= Bioretention (cell or planter with underdrains)		50%	50%	0%	Bioret w/ underdrain	50/	00/	EL LILL : MANUALO D
0%	Non-infiltrating facilities	FC#1- Level 1	Permeable pavement facility (with underdrain)	NA	0%	20%	NA	(modeled)	5%	0%	Flow modeled using WWHM3 Pro.
0% 0%	Impervious surface reduction methods  Runoff reduction methods	FC#1- Level 2 FC#1- Level 3	Green roof Dispersion	NA NA	22% 54%	44% 85%	NA NA	Green Roof (modeled)  Dispersion (modeled)	17% 35%	0% 0%	Flow modeled using WWHM3 Pro. Flow modeled using WWHM3 Pro.
	Infiltration and reuse facilities	FC#1- Level 4	Bioretention (cell or planter without underdrains)	NA	91%	58%	NA	Bioret w/o underdrain	37%	0%	Flow modeled using WWHM3 Pro.
<u>0%</u> 0%	Infiltration and reuse facilities	FC#1- Level 5	Permeable pavement facility (without underdrain)  Rainwater harvesting	NA NA	91 /6 NA	NA	NA NA	(modeled) Professional Judgment	50%	0%	Credit based on professional judgment.
Flow Control #3 (FC#3) - Pre-		FC#1- Level 5	Namwater narvesting	INA	INA	NA NA	INA	Troideoichiaí dadginioin	30 %	0 /8	Credit based on professional judgment.
	2-year to 50-year flow duration to forest c	ondition									
Basin types: Some creek bas			Weighting=	15%	30%	30%	25%				
	Impervious surface reduction methods	FC#3- Level 1	Green roof	0%	25%	47%	68%		19%	0%	Flow and water quality performance evaluated based on
0%	impervious surface reduction metrious	1 C#3- Level 1	GleenTool	0 /8	2376	47 /6	08 /8	Professional Judgment	1976	0 78	results for pre-developed pasture and professional judgmen
	Traditional stormwater infrastructure		Detention cistern Detention vault								Flow and water quality performance evaluated based on
0%	(non-infiltrating facilities)	FC#3- Level 2	Detention pipe	0%	0%	83%	98%	Professional Judgment	25%	0%	results for pre-developed pasture and professional judgmer
078	Traditional starmwater infrastructure		Detention pond (with impermeable liner)  Infiltration trench		1				†		Clay and water quality performance avaluated based on
0%	Traditional stormwater infrastructure (small-scale/distributed infiltrating facilities)	FC#3- Level 3	Dry well	100%	100%	100%	33%	Professional Judgment	42%	0%	Flow and water quality performance evaluated based on results for pre-developed pasture and professional judgmer
			Bioretention (cell or planter without underdrains)								Flow and water quality performance evaluated based on
0%	Infiltration and reuse facilities	FC#3- Level 4	Permeable pavement facility (without underdrain)	100%	100%	100%	33%	Professional Judgment	42%	0%	results for pre-developed pasture and professional judgmer
0%	Infiltration and reuse facilities	FC#3- Level 5	Rainwater harvesting	NA	NA	NA	NA	Professional Judgment	50%	0%	Credit based on professional judgment.
Flow Control #4 (FC#4) - Pre-											
	2-year to 2-year flow duration to pasture of	condition		,							
Basin types: Some creek bas		1.	Weighting=		30%	45%	10%				Flow modeled using WWHM3 Pro. Water quality
0%	Impervious surface reduction methods	FC#4- Level 1	Green roof	0%	22%	44%	65%	Green Roof (modeled)	17%	0%	performance estimated based on professional judgment.
	Traditional stormwater infrastructure	FC#4- Level 2	Detention cistern Detention vault	0%	0%	80%	95%	Vault (modeled)	23%	0%	Sized using SPU Vault spreadsheet. Flow control modeled using WWHM3 Pro. Water quality performance based on
0%	(non-infiltrating facilities)	FG#4- Level 2	Detention pipe Detention pond (with impermeable liner)	0%	0%	80%	95%	vault (modeled)	23 /6	0 /8	professional judgment.
	Traditional stormwater infrastructure	FC#4- Level 3	Infiltration trench	98%	98%	99%	30%	Infiltration Trench	46%	0%	Flow modeled using WWHM3 Pro. Water quality
0%	(small-scale/distributed infiltrating facilities)		Dry well Bioretention (cell or planter without underdrains)	<b>.</b>	<del> </del>	<del></del>	1	(modeled) Infiltration Trench			performance based on volume reduction (% infiltration). Flow modeled using WWHM3 Pro. Water quality
0%	Infiltration and reuse facilities	FC#4- Level 4	Permeable pavement facility (without underdrain)	98%	98%	99%	30%	(modeled)	46%	0%	performance based on volume reduction (% infiltration).
0% Flow Control #5 (FC#5) - Pea	Infiltration and reuse facilities	FC#4- Level 5	Rainwater harvesting	NA	NA	NA	NA	Professional Judgment	50%	0%	Credit based on professional judgment.
Flow Control #5 (FC#5) - Peak Flow Control Design Standard: 2- and 25-year peak control											
	d sewer, capacity-constrained, small lake	S	Weighting=	= 0%	25%	40%	35%				
			Detention cistern								Cined using CDII Voult pared to the Country of the
	Traditional stormwater infrastructure (non-infiltrating facilities)	FC#5- Level 1	Detention vault Detention pipe	NA	0%	48%	63%	Vault (modeled)	21%	0%	Sized using SPU Vault spreadsheet. Flow modeled using WWHM3 Pro.
0% 0%	Impervious surface reduction methods	FC#5- Level 2	Detention pond (with impermeable liner)  Green roof	NA	22%	44%	65%	Green Roof (modeled)	23%	0%	Flow modeled using WWHM3 Pro.
	Non-infiltrating facilities	FC#5- Level 3	Bioretention (cell or planter with underdrains)	NA NA	0%	75%	80%	Bioret w/ underdrain	29%	0%	Flow modeled using WWHM3 Pro.
0%	Traditional stormwater infrastructure		Permeable pavement facility (with underdrain) Infiltration trench	1		<del></del>	1	(modeled) Infiltration Trench			<u> </u>
0%	(small-scale/distributed infiltrating facilities)	FC#5- Level 4	Dry well	NA	98%	100%	64%	(modeled)	44%	0%	Flow modeled using WWHM3 Pro.
0%	Infiltration and reuse facilities	FC#5- Level 5	Bioretention (cell or planter without underdrains) Permeable pavement facility (without underdrain)	NA	98%	100%	64%	Infiltration Trench (modeled)	44%	0%	Flow modeled using WWHM3 Pro.
			pavomont identy (without underdialit)					(modeled)			

0%	Infiltration and reuse facilities	FC#5- Level 6	Rainwater harvesting	NA	NA	NA	NA	Professional Judgment	50%	0%	Credit based on professional judgment.
<b>Rainwater Harvesting Cred</b>	ainwater Harvesting Credit for Commercial Properties -% of Roof Area										
0%	Infiltration and reuse facilities	NA	Rainwater harvesting (commercial)	NA	NA	NA	NA		10%	0%	Commercial properties only
Total Adjusted Facility Credit								d Facility Credit	0.0%		

Final Parcel Credit Calculation	
Total Adjusted Facility Credit	0%
Rate Tier Multiplier (3)	0%
Final Parcel Credit (4)	0%

### Notes:

FC5 only

- 1) The facility credit is the scaled weighted average of the percent reductions by performance target.
- 2) The adjusted facility credit is the facility credit multiplied by the percentage of total impervious area managed by the applicable facility.
- 3) The rate tier multiplier is the percentage of the customer's bill attributable to impervious area runoff. Credit is only offered for runoff managed which originates on impervious surface.
- 4) The final parcel credit is the rate tier multiplier multiplied by the sum of a property's adjusted facility credits (i.e., the "total adjusted facility credit"). The final parcel credit is capped at 50%. The final parcel credit is the credit percentage applied to the customer bill.
- 5) For the water quality treatment PGIS/impervious area, enter PGIS as a percent of the total impervious area.
- 6) Where flow control is provided, it is estimated that 75% of the total impervious surface is managed. This is based upon past business inspections.
- 7) Fractional credits are not offered note that no credit will be offered for credits that are calculated to round to less than 1%.
- 8) FC1 applies to all parcels. Possible basin combinations include:

WQ only	WQ and FC3	FC3 and FC5
FC1 only	WQ and FC4	FC4 and FC5
FC3 only	WQ and FC5	
FC4 only	WQ and FC3 and FC5	

WQ and FC4 and FC5

9) Flow Control 2 (FC2) - Wetland Protection requirements may also apply. A separate credit will be calculated outside of this calculator if necessary.

- 10) A separate credit will be calculated for infiltration basins (or other traditional stormwater infrastructure) outside of this calculator if necessary.
- 11) Applicable standards will depend on project type, size, and drainage basin (see Vol III, Section 2.5.3)
- 12) TSS is used as an indicator of water quality treatment; Volume is used as an indicator of volume reduction via infiltration or reuse.

Rate Tier Multipliers		% Impervious or Parcel Area	Tier	Multiplier (3)
General Service/Large Residential	Undeveloped-Regular	0-15%	G1	30%
	Undeveloped-Low Impact	0-15%	G1L	23%
	Light-Regular	16-35%	G2	63%
	Light-Low Impact	16-35%	G2L	62%
	Moderate-Regular	36-65%	G3	83%
	Moderate-Low Impact	36-65%	G3L	79%
	Heavy	66-85%	G4	93%
	Very Heavy	86-100%	G5	99%
Small Residential		<2,000 sq ft	R1a	85%
		2,000-2,999 sq ft	R1b	84%
		3,000-4,999 sq ft	R2	79%
		5,000-6,999 sq ft	R3	78%
		7,000-9,999 sq ft	R4	74%
	a entry regarding Rate Tier and % imperviou		aged.	
	tage for impervious area served by each BM			
Mult Lookup Table to convert imperviou	s area impacts of facility to composite Rate	Credit Percentage.		

Rate Credit percentage that will appear on and modify bills, reflecting applicant facilities, their

sizes and the Rate Tier of the applying parcel.

# Attachment A - Table 3 . Stormwater Facility Credit Program (SFCP) Credit Calculator: For Facilities Built According to 2016 Seattle Code Requirements

Drainage Rate Tier:		1		ı		Performar	nce Factors		Facility Credit		
% Hard Surface Area Managed (see note 1)	WQ/FC	Stormwater Facility Type			TSS Reduction		2-yr Peak Flow & Duration Reduction	25-yr Peak Flow Reduction	Facility Credit (see note 2)	Adjusted Facility Credit (see note 3)	
Water Quality (WQ)	Olucomoution	otorniwater racinty type			reduction	Reduction	reduction	reduction	note 2)	(300 11010 0)	
	he water qua	lity design storm volume or flow r	ate								
Basin types: Basins requiring be	•	_ ·		Weighting Factor=	60%	40%	0%	0%			
0%	WQ- Level 1	Non-infiltrating bioretention     Biofiltration swale (basic, wet, continuous inflow or compost amended)     Filter strip (basic or compost amended)	<ul><li>Linear sand filter</li><li>Wet pond</li></ul>	Stormwater treatment wetland Detention/wet pond Detention/wet vault Detention/stormwater wetland Proprietary BMPs	81%	20%	NA	NA	29%	0%	
0%	WQ- Level 2	Media filter drain     Infiltration trench     Infiltrating bioretention (with or without underdrain)     Permeable pavement facility	Wet vault     Permeable pavement surface     Infiltration basin     Infiltration chamber	Splashblock, trench, sheet flow, or concentrated flow dispersion meeting basic filter strip requirements	94%	94%	NA	NA	47%	0%	
Flow Control #1 (FC#1) - On-site	Stormwater	Management									
<b>Design Standard: On-site Perfor</b>	mance Stand	ard or On-site List Approach									
Basin types: All				Weighting Factor=	15%	35%	40%	10%			
0%	FC#1- Level 1	Single-family residential cistern     Perforated stub-out connection			13%	10%	11%	27%	7%	0%	
0%	FC#1- Level 2	Vegetated roof     Sheet flow dispersion	Concentrated flow dispersion     Splashblock downspout dispersion	Trench downspout dispersion     Non-infiltrating historytaping	58%	25%	60%	70%	24%	0%	
0%	FC#1- Level 3	Rain garden     Infiltrating bioretention (with or without	Permeable pavement facility     Permeable pavement surface	Non-infiltrating bioretention     Rainwater harvesting	95%	90%	83%	28%	41%	0%	
0%	FC#1- Level 4	underdrain)  • Full dispersion	• Dry well		98%	93%	89%	52%	44%	0%	
Flow Control #2 (FC#2) - Wetlan		Infiltration trench			0070	33,0	3070	32,0	11,0	• 7.0	
		20 percent of the pre project value	no during a single event and wi	thin 15 percent on a monthly basis.							
Basin types: Wetlands	olume within	20 percent of the pre-project volui	ne during a single event and wi	Weighting Factor=	15%	30%	30%	25%			
	50#2 1 xxx14	Vegetated roofs	Detention pipe	Detention/ wet pond					220/	00/	
0%	FC#2- Level 1	Detention cistern     Detention vault	Detention pond (with impermeable liner)	Detention/ wet vault     Detention/ stormwater wetland	55%	0%	57%	82%	23%	0%	
0%	FC#2- Level 2	Sheet flow dispersion     Concentrated flow dispersion	Splashblock downspout dispersion     Trench downspout dispersion	<ul><li>Permeable pavement facility</li><li>Permeable pavement surface</li></ul>	96%	84%	89%	40%	38%	0%	
0%	FC#2- Level 3	Infiltrating bioretention (without underdrain)     Full dispersion     Infiltration trench	Dry well     Infiltration chamber	Infiltration basin     Rainwater harvesting	99%	99%	96%	61%	45%	0%	
Flow Control #3 (FC#3) - Pre-dev	veloped Fores										
•	•	r flow duration to forested condition	on								
Basin types: Creek basins	•			Weighting Factor=	15%	30%	30%	25%			
0%	FC#3- Level 1	Vegetated roofs     Detention cistern     Detention vault	Detention pipe     Detention pond (with impermeable liner)	Detention/ wet pond     Detention/ wet vault     Detention/ stormwater wetland	55%	3%	46%	93%	23%	0%	
0%	FC#3- Level 2	Sheet flow dispersion     Concentrated flow dispersion	Splashblock downspout dispersion     Trench downspout dispersion	Permeable pavement facility     Permeable pavement surface	94%	82%	87%	40%	38%	0%	
0%	FC#3- Level 3	Infiltrating bioretention (without underdrain)     Full dispersion     Infiltration trench	Dry well     Infiltration chamber	Infiltration basin     Rainwater harvesting	100%	100%	97%	77%	47%	0%	
Flow Control #4 (FC#4) - Pre-dev	•	ire									
_	ear to 2-year	flow duration to pasture condition									
Basin types: Creek basins		Vegetated roofs		• Detention/ wet pond	15%	30%	45%	10%			
0%	FC#4- Level 1	<ul><li>Detention cistern</li><li>Detention vault</li></ul>	Detention pipe     Detention pond (with impermeable liner)	Detention/ wet vault     Detention/ stormwater wetland	55%	0%	57%	82%	21%	0%	
0%	FC#4- Level 2	<ul><li>Sheet flow dispersion</li><li>Concentrated flow dispersion</li></ul>	<ul><li>Splashblock downspout dispersion</li><li>Trench downspout dispersion</li></ul>	Permeable pavement facility     Permeable pavement surface	96%	84%	89%	40%	42%	0%	
0%	FC#4- Level 3	Infiltrating bioretention (without underdrain)     Full dispersion     Infiltration trench	Dry well     Infiltration chamber	Infiltration basin     Rainwater harvesting	99%	99%	96%	61%	47%	0%	

## Attachment A - Table 3 . Stormwater Facility Credit Program (SFCP) Credit Calculator: For Facilities Built According to 2016 Seattle Code Requirements

Drainage Rate Tier:							Performand	e Factors		Facility C	redit
% Hard Surface Area Managed (see note 1)	WQ/FC Classification	Stormwater Facility Type				TSS Reduction	Runoff Volume Reduction	-yr Peak Flow & Duration Reduction	25-yr Peak Flow Reduction	Facility Credit (see note 2)	Adjusted Facility Credit (see note 3)
	w Control #5 (FC#5) - Peak Control										
Design Standard: 2- and 25-year	r peak control										
Basin types: Public combined s	ewer, capacit	y-constrained, small lakes			Weighting=	0%	25%	40%	35%		
0%	FC#5- Level 1	Detention cistern     Detention vault     Detention pipe	<ul> <li>Detention pond (with impermeable liner)</li> <li>Detention/ wet pond</li> <li>Detention/ wet vault</li> </ul>	<ul> <li>Detention/ stormwater wetland</li> <li>Non-infiltrating bioretention</li> <li>Vegetated roofs</li> </ul>		NA	2%	90%	80%	33%	0%
0%	FC#5- Level 2	<ul><li>Sheet flow dispersion</li><li>Concentrated flow dispersion</li></ul>	<ul><li>Splashblock downspout dispersion</li><li>Trench downspout dispersion</li></ul>	<ul><li>Permeable pavement facility</li><li>Permeable pavement surface</li></ul>		NA	85%	85%	52%	37%	0%
0%	FC#5- Level 3	<ul> <li>Infiltrating bioretention (with or without underdrain)</li> <li>Full dispersion</li> <li>Infiltration trench</li> </ul>	Dry well     Infiltration chamber	Infiltration basin     Rainwater harvesting		NA	100%	100%	89%	48%	0%
	Total Adjusted Facility Credit									0.0%	

Final Parcel Credit Calculation	
Total Facility Credit	0%
Rate Tier Multiplier (see note 4)	0%
Final Parcel Credit (see note 5)	0%

#### Notes:

- 1) For the water quality standard, enter PGHS treated as a percent of the total hard surface area. For the flow control standard(s), enter hard surface area managed as a percent of the total hard surface area.
- 2) The "Facility Credit" a scaled weighted average of the performance factors for a given facility and performance standard. "Weighting Factors" assign greater or lesser weight to each performance factor relative to the environmental priorities for the type of basin in which the project is located.
- 3) The "Adjusted Facility Credit" is the "Facility Credit" multiplied by the "% Hard Surface Managed" by the facility.
- 4) The "Drainage Rate Tier Multiplier" is the percentage of the customer's bill attributable to hard surface area runoff. Credit is only offered for runoff managed which originates on hard surface.
- 5) The "Final Parcel Credit" is the "Drainage Rate Tier Multiplier" multiplied by the sum of a property's "Adjusted Facility Credits" (i.e., the "Total Adjusted Facility Credit").

  The final parcel credit is capped at 50%. The "Final Parcel Credit" is the credit percentage applied to the customer bill.
- 6) Fractional credits are not offered no credit will be offered for credits that are calculated to round to less than 1%.
- 7) Applicable standards will depend on project type, size, and drainage basin (see Volume I, Chapter 4 and 5).
- 8) TSS is used as an indicator of water quality treatment; Volume is used as an indicator of volume reduction via infiltration or reuse.
- 9) If multiple flow control standards apply to a project, the largest applicable credit is applied (e.g., if an area is mitigated for FC#1, FC#4 and FC#5, enter the % hard surface managed under the flow control standard that provides the highest credit for the facility used).
- 10) If both flow control and water quality standards apply to a project, credit will be given for both (e.g., if an area meets both treatment and flow control standards, enter the % hard surface managed under both the water quality and flow control standards- the resulting "% Hard Surface Managed" may exceed 100%).

age Rate Category		% Impervious or Parcel Area	Drainage Rate Tier	Drainage Rate Multiplier (see note 4)
al Service/Large Residential	Undeveloped-Regular	0-15%	G1	30%
	Undeveloped-Low Impact	0-15%	G1L	23%
	Light-Regular	16-35%	G2	63%
	Light-Low Impact	16-35%	G2L	62%
	Moderate-Regular	36-65%	G3	83%
	Moderate-Low Impact	36-65%	G3L	79%
	Heavy	66-85%	G4	93%
	Very Heavy	86-100%	G5	99%
Residential		<2,000 sq ft	R1a	85%
		2,000-2,999 sq ft	R1b	84%
		3,000-4,999 sq ft	R2	79%
		5,000-6,999 sq ft	R3	78%
		7,000-9,999 sq ft	R4	74%
Customer/applicant data e	ntry (Rate Tier and % impervi	7,000-9,999 sq ft	R4	

Lookup Table to convert impervious area impacts of facility to composite Rate Credit Percentage.

Rate Credit that will appear on and modify bills, reflecting stormwater facilities and Rate Tier.

DWW-260.2, Stormwater Facility Credit Calculator, eff. January 1, 2017

15%

## 2021 Stormwater Facility Credit Program (SFCP) Credit Calculator: For Facilities Built According to 2021 Seattle Code Requirements

Version: 07-23-21

Version: 07-23-21		_									
Drainage Rate Tier:						T	Facility Credit				
% Hard Surface Area Managed (see note 1)	WQ/FC Classification	Stormwater Facility Type			TSS Reduction	Runoff Volume Reduction	2-yr Peak Flow & Duration Reduction	25-yr Peak Flow Reduction	Weighted Performance Factor (see note 2)	Facility Credit (see note 3)	Adjusted Facility Credit (see note 4)
(ccc nete 1)	11 411 5 514001110411011	otorniwater ruemty rype							Credit Scaling Factor=	50%	(ccc netc 1)
Water Quality (WQ) (see note 12)	<u>'</u> )										
Design Standard: Treatment of t		gn storm volume or flow rate									
Basin types: Basins requiring ba	asic, enhanced, or ph	osphorus treatment		Weighting Factor=	60%	40%	0%	0%			
		Non-infiltrating bioretention     Biofiltration swale (basic, wet, continuous)	Basic or large sand filter basin     Sand filter vault	Stormwater treatment wetland     Detention/wet pond							
0%	WQ- Level 1	inflow, or compost amended) • Filter strip (basic or compost amended)	<ul><li>Linear sand filter</li><li>Wet pond</li></ul>	Detention/wet vault     Detention/stormwater wetland	81%	20%	NA	NA	57%	29%	0%
0%	WQ- Level 2	Media filter drain     Infiltration trench     Infiltrating bioretention	Wet vault     Permeable pavement surface     Infiltration basin	Proprietary BMPs     Splashblock, trench, sheet flow, or concentrated flow dispersion meeting basic	94%	94%	NA	NA	94%	47%	0%
Flance O a return I #4 (FO#4)	Ota-manata-Manasa-	Permeable pavement facility	Infiltration chamber	filter strip requirements							
Flow Control #1 (FC#1) - On-site Design Standard: On-site Perfor Basin types: All				Weighting Factor=	15%	35%	40%	10%			
0%	FC#1- Level 1	Single-family residential cistern				T	I I		13%	70/	09/
0%	FC#1- Level 1	Perforated stub-out connection     Vegetated roof	Rainwater harvesting (Runoff Volume Reduction of 25% or more, On-site List		13% 36%	10%	11% 27%	27% 41%	26%	7% 13%	0%
		Non-infiltrating bioretention     Trench downspout dispersion	Category 4)  Concentrated flow dispersion								
0%	FC#1- Level 3	Sheet flow dispersion	Splashblock downspout dispersion		91%	55%	86%	77%	75%	38%	0%
0%	FC#1- Level 4 (see note 13)	Rain garden     Infiltrating bioretention	<ul><li>Permeable pavement facility</li><li>Permeable pavement surface</li></ul>	Rainwater harvesting (On-site Performance Standard, On-site List Category 2)	95%	90%	83%	27%	82%	41%	0%
0%	FC#1- Level 5	Full dispersion     Infiltration trench	• Drywell		98%	93%	89%	51%	88%	44%	0%
Flow Control #2A (FC#2A) - Wetl	land Protection Metho		age Modeling								
*				water Management Manual for Wes	tern Washin	gton (Ecology	2019)				
Basin types: Wetlands	, ,		65	Weighting Factor=		30%	30%	25%			
,		Vegetated roofs	Detention pipe	Detention/ wet pond	550/	201	100/	000/	400/	222/	207
0%	FC#2A- Level 1	Detention cistern     Detention vault	Detention pond (with impermeable liner)	Detention/ wet vault     Detention/ stormwater wetland	55%	3%	46%	93%	46%	23%	0%
0%	FC#2A- Level 2	Sheet flow dispersion     Concentrated flow dispersion	Splashblock downspout dispersion     Trench downspout dispersion	Permeable pavement facility     Permeable pavement surface	93%	81%	87%	37%	74%	37%	0%
0%	FC#2A- Level 3	Infiltrating bioretention     Full dispersion     Infiltration trench	Infiltration chamber	Infiltration basin     Rainwater harvesting	100%	100%	97%	75%	93%	47%	0%
Flow Control #2B (FC#2B) - Wetl	land Protection Metho	d 2: Site Discharge Modeling									
Design Standard: Total runoff vo	olume within 20 perce	nt of the pre-project volume du	ring a single event and within 15	percent on a monthly basis							
Basin types: Wetlands				Weighting Factor=	15%	30%	30%	25%			
0%	FC#2B- Level 1	<ul><li> Vegetated roofs</li><li> Detention cistern</li><li> Detention vault</li></ul>	Detention pipe     Detention pond (with impermeable liner)	<ul> <li>Detention/ wet pond</li> <li>Detention/ wet vault</li> <li>Detention/ stormwater wetland</li> </ul>	55%	0%	57%	82%	46%	23%	0%
0%	FC#2B- Level 2	Sheet flow dispersion     Concentrated flow dispersion	Splashblock downspout dispersion     Trench downspout dispersion	Permeable pavement facility     Permeable pavement surface	96%	84%	89%	38%	76%	38%	0%
0%	FC#2B- Level 3	Infiltrating bioretention     Full dispersion	Drywell     Infiltration chamber	Infiltration basin     Rainwater harvesting	99%	99%	96%	61%	89%	45%	0%
Flow Control #3 (FC#3) - Pre-dev	veloped Forested	Infiltration trench									
Design Standard: Match half 2-y	•	ration to forested condition									
Execution of the contract of t											
	real to 30-year flow ut	iration to lorested condition		Weighting Factor=	15%	30%	30%	25%			
_	FC#3- Level 1	Vegetated roofs Detention cistern	Detention pipe     Detention pond (with impermeable liner)	Weighting Factor=  • Detention/ wet pond  • Detention/ wet vault	<b>15%</b> 55%	30%	<b>30%</b> 46%	<b>25%</b> 93%	46%	23%	0%
Basin types: Creek basins	•	Vegetated roofs     Detention cistern     Detention vault     Sheet flow dispersion	Detention pond (with impermeable liner)     Splashblock downspout dispersion	Detention/ wet pond     Detention/ wet vault     Detention/ stormwater wetland     Permeable pavement facility		I			46% 74%	23%	0%
Basin types: Creek basins 0%	FC#3- Level 1	Vegetated roofs Detention cistern Detention vault	Detention pond (with impermeable liner)     Splashblock downspout dispersion     Trench downspout dispersion     Drywell	Detention/ wet pond Detention/ wet vault Detention/ stormwater wetland Permeable pavement facility Permeable pavement surface Infiltration basin	55%	3%	46%	93%			
Basin types: Creek basins  0%  0%  0%	FC#3- Level 1 FC#3- Level 2 FC#3- Level 3	Vegetated roofs Detention cistern Detention vault Sheet flow dispersion Concentrated flow dispersion Infiltrating bioretention	Detention pond (with impermeable liner)     Splashblock downspout dispersion     Trench downspout dispersion	Detention/ wet pond Detention/ wet vault Detention/ stormwater wetland Permeable pavement facility Permeable pavement surface	55% 93%	3% 81%	46% 87%	93%	74%	37%	0%
Basin types: Creek basins  0%  0%  0%  Flow Control #4 (FC#4) - Pre-dev	FC#3- Level 1  FC#3- Level 2  FC#3- Level 3  veloped Pasture	Vegetated roofs Detention cistern Detention vault Sheet flow dispersion Concentrated flow dispersion Infiltrating bioretention Infiltration trench	Detention pond (with impermeable liner)     Splashblock downspout dispersion     Trench downspout dispersion     Drywell	Detention/ wet pond Detention/ wet vault Detention/ stormwater wetland Permeable pavement facility Permeable pavement surface Infiltration basin	55% 93%	3% 81%	46% 87%	93%	74%	37%	0%
Basin types: Creek basins  0%  0%  0%  Flow Control #4 (FC#4) - Pre-dev Design Standard: Match half 2-y	FC#3- Level 1  FC#3- Level 2  FC#3- Level 3  veloped Pasture	Vegetated roofs Detention cistern Detention vault Sheet flow dispersion Concentrated flow dispersion Infiltrating bioretention Infiltration trench	Detention pond (with impermeable liner)     Splashblock downspout dispersion     Trench downspout dispersion     Drywell	Detention/ wet pond Detention/ wet vault Detention/ stormwater wetland Permeable pavement facility Permeable pavement surface Infiltration basin Rainwater harvesting	55% 93% 100%	3% 81% 100%	46% 87% 97%	93% 37% 75%	74%	37%	0%
Basin types: Creek basins  0%  0%  0%  Flow Control #4 (FC#4) - Pre-dev Design Standard: Match half 2-y	FC#3- Level 1  FC#3- Level 2  FC#3- Level 3  veloped Pasture	Vegetated roofs Detention cistern Detention vault Sheet flow dispersion Concentrated flow dispersion Infiltrating bioretention Full dispersion Infiltration trench	Detention pond (with impermeable liner)     Splashblock downspout dispersion     Trench downspout dispersion      Drywell     Infiltration chamber	Detention/ wet pond Detention/ wet vault Detention/ stormwater wetland Permeable pavement facility Permeable pavement surface Infiltration basin Rainwater harvesting  Weighting Factor=	55% 93% 100%	3% 81%	46% 87%	93%	74%	37%	0%
Basin types: Creek basins 0% 0%	FC#3- Level 1  FC#3- Level 2  FC#3- Level 3  veloped Pasture	Vegetated roofs Detention cistern Detention vault Sheet flow dispersion Concentrated flow dispersion Infiltrating bioretention Full dispersion Infiltration trench  ation to pasture condition  Vegetated roofs Detention cistern Detention vault	Detention pond (with impermeable liner)  Splashblock downspout dispersion Trench downspout dispersion  Drywell Infiltration chamber  Detention pipe Detention pond (with impermeable liner)	Detention/ wet pond Detention/ wet vault Detention/ stormwater wetland Permeable pavement facility Permeable pavement surface Infiltration basin Rainwater harvesting  Weighting Factor= Detention/ wet pond Detention/ wet vault Detention/ stormwater wetland	55% 93% 100%	3% 81% 100%	46% 87% 97%	93% 37% 75%	74%	37%	0%
Basin types: Creek basins  0%  0%  0%  Flow Control #4 (FC#4) - Pre-dev Design Standard: Match half 2-y Basin types: Creek basins	FC#3- Level 1  FC#3- Level 2  FC#3- Level 3  veloped Pasture /ear to 2-year flow dur	Vegetated roofs Detention cistern Detention vault Sheet flow dispersion Concentrated flow dispersion Infiltrating bioretention Infiltration trench  Vegetated roofs Detention cistern	Detention pond (with impermeable liner)  Splashblock downspout dispersion Trench downspout dispersion  Drywell Infiltration chamber  Detention pipe	Detention/ wet pond Detention/ wet vault Detention/ stornwater wetland Permeable pavement facility Permeable pavement surface Infiltration basin Rainwater harvesting  Weighting Factor= Detention/ wet pond Detention/ wet vault	55% 93% 100%	3% 81% 100%	46% 87% 97%	93% 37% 75%	74% 93%	37% 47%	0%

2021 SFCP Calculator, Version 7-23-2021

Drainage Rate Tier:							Performance F	actors		Facilit	y Credit
% Hard Surface Area Managed					TSS	Runoff Volume	2-yr Peak Flow 8 Duration	& 25-yr Peak	Weighted Performance Factor	Facility Credit	Adjusted Facility Credit
(see note 1)	WQ/FC Classification	Stormwater Facility Type			Reducti	n Reduction	Reduction	Flow Reduction	(see note 2)	(see note 3)	(see note 4)
								Facility	Credit Scaling Factor=	50%	
Flow Control #5 (FC#5) - Peak Co	ontrol										
Design Standard: 2- and 25-year	peak control										
Basin types: Public combined se	wer, capacity-constr	ained, small lakes		Weigh	hting= 0%	25%	40%	35%			
0%	FC#5- Level 1	Detention cistern     Detention vault     Detention pipe	Detention pond (with impermeable liner)     Detention/ wet pond     Detention/ wet vault	Detention/ stormwater wetland     Vegetated roofs	NA	3%	94%	92%	71%	36%	0%
0%	FC#5- Level 2	Sheet flow dispersion     Concentrated flow dispersion	<ul><li>Splashblock downspout dispersion</li><li>Trench downspout dispersion</li></ul>	<ul><li>Permeable pavement facility</li><li>Permeable pavement surface</li></ul>	NA	85%	85%	59%	76%	38%	0%
0%	FC#5- Level 3	Infiltrating bioretention     Full dispersion     Infiltration trench	Drywell     Infiltration chamber	Infiltration basin     Rainwater harvesting	NA	99%	100%	89%	96%	48%	0%
					•		•		Total Adjust	ed Facility Credit	0.0%

Total Adjus						
Final Parcel Credit Calculation	Drainage Rate Category	% Impervious or Parcel Area	Drainage Rate Tier	Drainage Rate Tier Multiplier (see note 5)		
Total Facility Credit 0%	General Service/Large Residential Undeveloped-Regular	0-15%	G1	30%		
Drainage Rate Tier Multiplier (see note 5) 0%	Undeveloped-Low Impact	0-15%	G1L	23%		
Final Parcel Credit (see note 6) 0%	Light-Regular	16-35%	G2	63%		
	Light-Low Impact	16-35%	G2L	62%		
Notes:	Moderate-Regular	36-65%	G3	83%		
1) For the water quality standard, enter PGHS treated as a percent of the total hard surface area. For the flow control standard(s), enter hard surface area managed as a	Moderate-Low Impact	36-65%	G3L	79%		
percent of the total hard surface area.	Heavy	66-85%	G4	93%		
2) The "Weighted Performance Factor" is the weighted average of the performance factors for a given facility and performance standard. "Weighting Factors" assign greater or lesser weight	Very Heavy	86-100%	G5	99%		
to each performance factor relative to the environmental priorities for the type of basin in which the project is located.	Small Residential	<2,000 sq ft	R1a	85%		
3) The "Facility Credit" is the "Weighted Performance Factor" multiplied by the Facility Credit Scaling Factor of 50%.		2,000-2,999 sq ft	R1b	84%		
4) The "Adjusted Facility Credit" is the "Facility Credit" multiplied by the "% Hard Surface Managed" by the facility.		3,000-4,999 sq ft	R2	79%		
5) The "Drainage Rate Tier Multiplier" is the percentage of the customer's bill attributable to hard surface area runoff. Credit is only offered for runoff managed which originates on hard surface.		5,000-6,999 sq ft	R3	78%		
6) The "Final Parcel Credit" is the "Drainage Rate Tier Multiplier" multiplied by the sum of a property's "Adjusted Facility Credits" (i.e., the "Total Adjusted Facility Credit").		7,000-9,999 sq ft	R4	74%		
The final parcel credit is capped at 50%. The "Final Parcel Credit" is the credit percentage applied to the customer bill.	Color Key:					
7) Fractional credits are not offered - no credit will be offered for credits that are calculated to round to less than 1%.						
8) Applicable standards will depend on project type, size, and drainage basin (see Volume 1, Chapters 4 and 5).	20% Customer/applicant data entry (Drainage Rate Tier and	% impervious or PGHS are	ea managed).			
9) TSS is used as an indicator of water quality treatment; Volume is used as an indicator of volume reduction via infiltration or reuse.						
10) If multiple flow control standards apply to a project, the largest applicable credit is applied (e.g., if an area is mitigated for FC#1, FC#4 and FC#5, enter the % hard surface managed	10% Stormwater Facility Credit					
under the flow control standard that provides the highest credit for the facility used).						
11) If both flow control and water quality standards apply to a project, credit will be given for both (e.g., if an area meets both treatment and flow control standards, enter the % hard surface	Tier/% Lookup Table to convert impervious area impacts of fac	Tier/% Lookup Table to convert impervious area impacts of facility to composite Rate Credit Percentage.				
managed under both the water quality and flow control standards - the resulting "% Hard Surface Managed" may exceed 100%).						
12) Landscape Management Plan areas do not receive Water Quality treatment credit because no stormwater facility is installed.	15% Rate Credit that will appear on and modify bills, reflection	ng stormwater facilities ar	nd Rate Tier.			
13) Sidewalk/Trail Compost-Amended Strip does not receive On-site Stormwater Management credit because it is not a facility and is equivalent to soil amendment required for all projects.						

2021 SFCP Calculator, Version 7-23-2021