# Northgate Stakeholders Group

# Thornton Creek Water Quality Channel

30% Design Review Summary

**Seattle Public Utilities** 

January 24, 2006



### **Presentation Overview**

- Background and Introductions (Miranda)
- Design Team Recommendations (Tom)
- Cost Review (Randy, Olympic Associates)
- Q&A (Miranda with Design Team)

### Background

#### 2004

- Feasibility and Evaluation
- Stakeholder Advice
- City Council approval
- Purchase Property

### 2005

Completed Engineering and 30% Design

### 30% Design Review

Oct 18th - Northgate Stakeholders, plus 2 discussions

Oct 12th - SPU Asset Management Committee

Oct 20<sup>th</sup> – Seattle Design Commission

Oct 20th – Stakeholder Forum



# 30% Design Review – Key Issues

- Landscape Design and Pedestrian Access
- Grading and Retaining Walls
- Water Quality and Channel Design
- Cost and Constructability Review

### Design Team Workshop Series

#### Purpose

- to review technical assumptions
- develop recommendations to address review comments

#### Design Team:

- Miranda Maupin, SPU, project lead
- Tom Fawthrop, SPU, project manager
- Masako Lo, SPU, design engineer
- Peggy Gaynor, Gaynor Inc., concept design
- Greg Giraldo, SvR, civil design
- Melanie Davies, SvR, landscape design

Dec 20th - SPU Executive Steering Committee, Presented Recommendations

#### Cost and Constructability Review

Randy Barber, Olympic Associates

### Project Goals and Stakeholder Advice

### **Project Goals**

- 1. Improve water quality for Thornton Creek
- 2. Provide pleasing public open space

### **Stakeholder Values**


- Moving water
- Aesthetics
- Safety
- Pedestrian movement
- Water quality
- Cost controls


### Key Issues:

- Desire for access to site from 100<sup>th</sup>
- Enhance qualities of pedestrian experience


#### Recommendations:

- Provide stairwell from 4<sup>th</sup> and 100<sup>th</sup> into site
- Enhance pedestrian experience
  - Enhance formal urban vs. informal natural areas
  - Ensure water views and sounds
- Enhance planting design
  - Create more variability in channel through planting
  - Emphasize formal and informal areas
  - Create more open views into channel
  - Create more open views for security









# Grading and Retaining Walls

### Issues:

Increase variability in walls

### Recommendations:

- Vary wall type
  - Use predominately green (MSE) walls
  - Use concrete for more formal areas to increase views to the water and create more variability in the channel
- Vary wall slope (batter) for green walls
  - Increases views to the water and variability

Grading and Retaining Walls





#### Issues:


- Create more variability in the channel by modifying the weir/level spreader design
- Use more natural materials for low-flow channel

#### Recommendations:

- Create series of 3 "wetland weirs" that provide rhythm between ponded wetland areas and low flow channel treatment swales
- Use plants and gravel to define the low flow channel














# Cost Constructability Review

- The job can be done
- The two phase approach makes sense
- Concur with decision to relocate the diversion weir due to cost and risk
- Costs in 4 major areas
  - Erosion control
  - Earthwork excavation and grading
  - Walls
  - Landscaping
- Not a lot of opportunity to reduce costs and maintain project goals and stakeholder values

### Recommendations

- Prioritize finalizing wall details and locations
- Prepare an updated cost estimate
- Monitor costs of excavation especially given uncertainties in the market (gas prices, etc.)
- Lock down design elements to maintain budget

# Next Steps

- Continue to refine the design team recommendations in 60% Design
- Develop an updated cost estimate
- Update Stakeholders at April meeting

# Project Schedule

- January 2006 Permit application
- April 2006 60% Design for Stakeholders
- June 2006 Earthwork Construction
- April 2007 Start Channel Construction
- November 2007 Substantial Completion
- April 2008 End Construction

### **Thornton Creek Water Quality Channel**

### **Q&A Discussion**

#### **Design Team:**

Miranda Maupin, SPU, project lead Tom Fawthrop, SPU, project manager Masako Lo, SPU, design engineer Peggy Gaynor, Gaynor Inc., concept design Greg Giraldo, SvR, civil design Melanie Davies, SvR, landscape design

#### **Cost and Constructability Reviewer:**

Randy Barber, Olympic Associates

### Northgate Stakeholders Group

**January 24, 2006**