



NW 90th Street - NW Holman Road to 8th Ave NW



NW 90th Street - NW Holman Road to 8th Ave NW



Project ID # 2007-463

Type of Improvement: Sidewalk
Neighborhood: Crown Hill

Approximate Length: 1650 feet
Street Classification: Local Street

Applicant Description of Problem and/or Project:

Problem: Pedestrian Safety/neighborhood walkability. Connects residential, 8th Ave NW buses / businesses with Crown Hill Cemetery, 85th St buses / businesses, Soundview Park / playfields, and Whitman Middle School. Safe routes to School: We have many families traveling to/from Whitman Middle School (NW 95th and 15th Ave NW), Whittier Elementary (NW 75th and 13th Ave NW), North Beach Elementary (NW 90th and 24th Ave NW) and Small Faces preschool (NW 95th and 13th Ave NW). Safe routes to local business and busses. Safe routes to parks and playfields. Soundview park & playfield, Crown Hill Elementary School park and playfield, Carkeek trail & Baker park. Safe routes for seniors and youth. Crown Hill/Ballard neighborhood Plan.

Suggested Project: Install sidewalks / boulevards.

Potential Solution and/or Comments:

NW 90th Street from NW Holman Rd to 12th Ave NW

- Construct concrete curb, gutter, 5-foot landscape planting strip and 6-foot concrete sidewalk on both sides of the street.
- Widen roadway 5 feet on both sides of the street to meet the City's standard street width of 25 feet.
- Construct new catch basins and storm sewer to collect street runoff.

NW 90th Street from 9th Ave NW to 8th Ave NW

- Construct concrete curb, gutter, 5-foot planting strip and 6-foot concrete sidewalk on both sides of the street.
- Widen roadway by a total of 5 feet to meet the City's standard street width of 25 feet.
- Construct new catch basins and storm sewer to collect street runoff.
- Relocate utility poles on the north side of street.

Challenges/Tradeoffs:

- No improvements will be made between 12th Ave NW and 9th Ave NW to avoid the need for additional right of way.
- Existing sidewalk on north side of street between 14th Ave NW and Mary Ave NW will not be replaced because it is in good condition.
- Street parking may be prohibited.
- Omitting the planting strip would reduce the overall cost of the project.

Preliminary Range of Cost: \$2,080,000 to \$2,560,000