


P:\c\cse40000016\0400C4D\T\DWG\Task 5 - S Dakota ST\Sheet\TS5392C_PS_P.dwg
Jul-26-12 11:36am



-  CEMENT CONCRETE SIDEWALK
 CURB REMOVAL

CONSTRUCTION NOTES

- (1) REMOVE EXISTING CURB TO LIMITS SHOWN ON PLAN.
- (2) REMOVE SIDEWALK TO NEAREST FULL DEPTH JOINT.
- (3) NOT USED, THIS SHEET.
- (4) NOT USED, THIS SHEET.
- (5) CONSTRUCT PERPENDICULAR CURB RAMP PER COS STANDARD PLAN NO. 422a AND DETAIL, THIS SHEET. SDOT CONSTRUCTION TO VERIFY CURB RAMP SLOPES ARE LESS THAN THE MAXIMUM SLOPES ALLOWED IN THE STANDARD PLAN PRIOR TO CONCRETE POUR.
- (6) CONSTRUCT SIDEWALK PER COS STANDARD PLAN NO. 420.
- (7) ADJUST WATER METER BOX TO FINISHED GRADE.

(CURB RAMP DETAILS TO BE PROVIDED AT 90% DESIGN)

(CURB RAMP DETAILS TO BE PROVIDED AT 90% DESIGN)

GENERAL NOTES

1. ALL BASEMAP AND GRADING INFORMATION IS APPROXIMATE.
2. SDOT CONSTRUCTION TO FIELD VERIFY LAYOUT OF PROPOSED IMPROVEMENTS AND NOTIFY ENGINEER OF ANY CONFLICTS OR DISCREPANCIES PRIOR TO CONSTRUCTION.
3. NOT ALL UTILITIES ARE SHOWN ON THE DRAWING. SDOT CONSTRUCTION SHALL NOTIFY THE UTILITIES FOR UNDERGROUND UTILITY LOCATIONS BEFORE THE COMMENCEMENT OF ANY EXCAVATION. ADVANCE NOTIFICATION IS REQUIRED.

SIDEWALK WIDENING S DAKOTA STREET



50% REVIEW
NOT FOR CONSTRUCTION
07/17/2012

APPROVED FOR ADVERTISING
NANCY LOCKE
DEPARTMENT OF FINANCE & ADMINISTRATIVE SERVICES
SEATTLE, WASHINGTON 20

BY: _____
PURCHASING & CONTRACTING SERVICES DIRECTOR

NAME OR INITIALS AND DATE		INITIALS AND DATE	
DESIGNED JMGE		REVIEWED:	
CHECKED SBS		DES. ###	CONST. ###
		SDOT ###	PROJ. MGR. ###
DRAWN JMGE		RECEIVED ###	
CHECKED SBS		REVISED AS BUILT ###	
ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE CITY OF SEATTLE STANDARD PLANS AND SPECIFICATIONS AND OTHER DOCUMENTS CALLED FOR IN SECTION 0-2.3 OF THE PROJECT MANUAL.			







ORDINANCE NO. APPROVED.
FUND:
SCALE: AS NOTED INSPECTOR'S BOOK

2012 SDOT SPOT IMPROVEMENTS PROJECT

JOB NO.	PC	TS53920
	R/W	
	CO	TS53920
VAULT PLAN NO.		
####		
SHEET	1	OF 2

P:\c\cse400000016\0400CAD\TT\DWG\Task 5 - S Dakota SI\Sheet\TS5392C_PS_P2.dwg
Jul-26-12 11:39am



-  HMA PG 64-22 PAVEMENT AREA
 CEMENT CONCRETE SIDEWALK
 SAWCUT FULL DEPTH
 CURB REMOVAL

GENERAL NOTES

1. ALL BASEMAP AND GRADING INFORMATION IS APPROXIMATE.
2. SDOT CONSTRUCTION TO FIELD VERIFY LAYOUT OF PROPOSED IMPROVEMENTS AND NOTIFY ENGINEER OF ANY CONFLICTS OR DISCREPANCIES PRIOR TO CONSTRUCTION.
3. NOT ALL UTILITIES ARE SHOWN ON THE DRAWING. SDOT CONSTRUCTION SHALL NOTIFY THE UTILITIES FOR UNDERGROUND UTILITY LOCATIONS BEFORE THE COMMENCEMENT OF ANY EXCAVATION. ADVANCE NOTIFICATION IS REQUIRED.

SIDEWALK WIDENING S DAKOTA STREET

CONSTRUCTION NOTES

- 1 REMOVE EXISTING CURB TO LIMITS SHOWN ON PLAN.
- 2 REMOVE SIDEWALK TO NEAREST FULL DEPTH JOINT.
- 3 REMOVE EXISTING TREE.
- 4 SAWCUT EXISTING ASPHALT PAVEMENT AND INSTALL TYPE 410B CURB OVER 6" OF MINERAL AGGREGATE TYPE 2. PATCH BACK WITH HMA CL 1/2" PG 64-22 PER ROADWAY SECTION THIS SHEET.
- 5 CONSTRUCT PERPENDICULAR CURB RAMP PER COS STANDARD PLAN NO. 422a AND DETAIL, THIS SHEET. SDOT CONSTRUCTION TO VERIFY CURB RAMP SLOPES ARE LESS THAN THE MAXIMUM SLOPES ALLOWED IN THE STANDARD PLAN PRIOR TO CONCRETE POUR.
- 6 CONSTRUCT SIDEWALK PER COS STANDARD PLAN NO. 420.
- 7 ADJUST WATER METER BOX TO FINISHED GRADE.
- 8 ADJUST WATER MANHOLE TO FINISHED GRADE.
- 9 RESTORE LANDSCAPE STRIP PER DIRECTION FROM SDOT URBAN FORESTRY.

(CURB RAMP DETAILS TO BE PROVIDED AT 90% DESIGN)

(CURB RAMP DETAILS TO BE PROVIDED AT 90% DESIGN)

CURB RAMP #3 DETAIL

SCALE: 1" = 10'

CURB RAMP #4 DETAIL

SCALE: 1" = 10'



**DAVID EVANS
AND ASSOCIATES INC.**
415 - 118th Avenue SE
Bellevue Washington 98005-3518
Phone: 425.519.6500

50% REVIEW
NOT FOR CONSTRUCTION
07/17/2012

APPROVED FOR ADVERTISING
NANCY LOCKE
DEPARTMENT OF FINANCE & ADMINISTRATIVE SERVICES
SEATTLE, WASHINGTON 20

BY: _____
PURCHASING & CONTRACTING SERVICES DIRECTOR

NAME OR INITIALS AND DATE		INITIALS AND DATE	
DESIGNED JMGE		REVIEWED:	
CHECKED SBS		DES. ###	CONST. ###
		SDOT ###	PROJ. MGR. ###
DRAWN JMGE		RECEIVED ###	
CHECKED SBS		REVISED AS BUILT ###	
ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE CITY OF SEATTLE STANDARD PLANS AND SPECIFICATIONS AND OTHER DOCUMENTS CALLED FOR IN SECTION 0-02.3 OF THE PROJECT MANUAL.			



City of Seattle
Seattle Department
of Transportation

ORDINANCE NO. APPROVED.
FUND:
SCALE: AS NOTED INSPECTOR'S BOOK.

2012 SDOT SPOT IMPROVEMENTS PROJECT

JOB NO. PC TS53920
R/W
CO TS53920
VAULT PLAN NO. #####
SHEET 2 OF 2