

# NE 130th - Lake City Way to 20th Ave NE & Olympic Hill School



# NE 130th - Lake City Way to 20th Ave NE & Olympic Hill School



**Project ID # 2007-018**

**Type of Improvement:** Sidewalk  
**Neighborhood:** Olympic Hills

**Approximate Length:** 2500 feet  
**Street Classification:** Local Street

## **Applicant Description of Problem and/or Project:**

**Problem:** Many children and parents walk to this school including many immigrant families who come to community events as well.

**Suggested Project:** Use the Safe Routes to Schools as matching funds to complete the entire stretch of sidewalk on the north side of the street.

## **Potential Solution and/or Comments:**

NE 130<sup>th</sup> from Lake City Way to 20<sup>th</sup> Ave NE and Olympic Hill School

- Construct concrete curb, gutter, and 6-foot concrete sidewalk on the north side of the street for approximately one third of a mile from 23<sup>rd</sup> Ave NE to 30<sup>th</sup> Ave NE.
- Construct concrete curb, gutter, and 6-foot concrete sidewalk on the north side of the street for approximately 400 feet from 30<sup>th</sup> Ave NE to 31<sup>st</sup> Ave NE.
- Widen the roadway 4 feet on the north side of the street from 23<sup>rd</sup> Ave NE to 28<sup>th</sup> Ave NE to meet the City's standard street width.
- Widen the roadway 1 foot on the north side of the street from 28<sup>th</sup> Ave NE to 30<sup>th</sup> Ave NE to meet the City's standard street width.
- Widen the roadway 6 feet on the north side of the street from 30<sup>th</sup> Ave NE to 31<sup>st</sup> Ave NE to meet the City's standard street width.
- Construct new catch basins and connecting stormwater conveyance system on the north side of the street to collect street runoff.
- Construct seven retaining walls on the north side of the street.

## **Challenges/Tradeoffs:**

- No planting strip is included in order to minimize the need for additional retaining walls.
- Utility pole relocation may be required and may make this project cost prohibitive.
- Existing private improvements within right-of-way such as landscaping, fences, walls, patios may require removal.
- Numerous small retaining walls needed because of steep slopes on the north side of the street.

**Preliminary Range of Cost:** \$ 1,480,000 to \$ 1,820,000

Bridging the Gap Neighborhood Street Fund Proposed Project

