PART 1 - GENERAL

1.01 SECTION INCLUDES:

A. This work includes furnishing, installing, operating, maintaining, and removal of temporary construction facilities.

1.02 TEMPORARY FACILITIES:

A. All costs associated with utilities and serviced required of the Contractor to execute the contract work shall be borne by the Contractor.

B. Meals and Lodging: The Owner will not provide meal and lodging facilities for the Contractor's personnel.

C. Temporary Buildings: The Contractor may construct or provide temporary buildings, at an approved or designated location, as may be necessary for the performance of the work. At the completion of the work, the Contractor shall remove all temporary buildings.

D. Toilet Facilities:

1. The Contractor shall provide and maintain adequate chemical toilet facilities for all individuals connected with the work, with separate facilities for men and women.

2. The Contractor shall keep the toilet facilities in sanitary condition in accordance with the King County Health Department.

3. The Contractor shall remove the toilet facilities at completion of the contract and shall disinfect the premises.

E. The Contractor shall make all necessary arrangements for temporary water, electrical, telephone and fire hydrant services. The Contractor shall obtain required hydrant use permits from the Seattle Public Utilities, Water Department.

F. The Contractor shall maintain the construction area in a neat and orderly condition throughout the contract. Food and garbage shall be stored properly to prevent attracting animals. Remove food and garbage from the site during non-work hours. Practice controls to stop rodent infestation of temporary facilities and the job site.

G. Staging and stockpiling areas will be determined in the pre-construction conference.

H. After completion of Work the Contractor shall remove all temporary facilities and shall restore the temporary facilities area to its original state.

1.03 MATERIAL DELIVERY AND STORAGE:

A. Delivery of materials shall be made only during the Contractor's working hours and at such times as they have a representative available.

B. The Contractor shall store materials within the work site area at an area determined in pre-construction conference or designated by the Engineer.

PART 2 - PRODUCTS

Not Used.

PART 3 - EXECUTION

Not Used.

END OF SECTION