PART 1 - GENERAL

1.01 SUMMARY OF WORK:

A. All workmanship and materials shall be subjected to inspection by the Engineer, who may select samples of materials in such number and quantities as he/she may deem necessary to determine their conformance with the specifications and project intent.

B. All rejected materials and work shall be promptly removed by the Contractor from the premises and adjacent surroundings.

C. All rejected work or materials shall be promptly replaced to the satisfaction of the Engineer.

D. The Engineer reserves the right to inspect any component of the work at any time. The items of work are being reviewed for conformance with the design intent as well as workmanship and quality of materials. The Contractor shall cooperate with the Engineer's inspections. When identified in Technical Specifications, notification shall be provided to the Engineer 48 hours in advance of the time the inspections are needed.

PART 2 - PRODUCTS: (Not Used)

PART 3 - EXECUTION

3.01 INSPECTION AND TESTING:

A. The Contractor shall furnish samples of materials for testing, if requested by the Engineer, at no additional cost. Tests by the Engineer will be made in accordance with commonly recognized standards of national materials testing organizations and any such other special methods as deemed necessary.

B. Any and all materials necessary for the construction of any part of the work and associated improvements not specified shall be of the best available quality acceptable to the Engineer.

3.02 SAMPLES:

A. The Contractor shall prepare and submit such samples as are required elsewhere in these specifications at such time as is necessary to allow sufficient time for retesting or modification of the work, at the Engineers discretion, based on evaluation of the samples.

3.03 FINAL INSPECTION:

A. Final inspection shall take place after all requirements for Substantial Completion have been completed, including all punch list items outlined in other Sections of these specifications. Final inspection of the work by the Engineer will be made no later than five (5) Working Days after receipt of Contractor's written request for final inspection.

B. Before Final Payment will be made, defects or omissions noted on the final inspection must be corrected by the Contractor without additional cost to the Owner. See Section 01 77 19 - Contract Closeout.

END OF SECTION