

WASHINGTON STREET BOAT LANDING

PIONEER SQUARE PRESERVATION BOARD SIGNAGE APPROVAL PACKAGE


MAY 2024

DESCRIPTION OF PROPOSED WORK


1. INSTALL SIGNAGE AT EXISTING WASHINGTON STREET BOAT LANDING BUILDING TO COMPLIMENT APPROVED ICE CREAM CONCESSION TENANT IMPROVEMENT. INCLUDES (1) EXTERNALLY LIT BLADE SIGN AND (1) METAL FRAMED NEON SIGN ON NORTH ELEVATION, AND (2) NEON SIGNS ON EAST ELEVATION.

ALL ATTACHMENTS AT HISTORIC METAL STRUCTURE TO BE MADE WITH CUSTOM FABRICATED NON MARRING CLAMPING ARMATURES. ATTACHMENTS AT (E) CLADDING TO BE PATCHED AND FILLED TO MATCH AT COMPLETION OF TENANCY.

NOTE LETTERS DO EXCEED ALLOWABLE SIZE PER PRESERVATION GUIDELINES. DUE TO THE SATELLITE NATURE OF THE STRUCTURE IN BOTH THE HISTORIC DISTRICT AND THE WATERFRONT PROMENADE, A VARIANCE IS REQUESTED TO ACHIEVE APPROPRIATE VISIBILITY. SEE VICINITY MAP, DIMENSIONING DETAILS AND RENDERINGS FOR CLARIFICATION.




PROPOSED ELEVATION - NORTH SCALE: 1/8" = 1'-0"




PROPOSED ELEVATION - EAST

SCALE: 1/8'' = 1'-0''

SITE MAP




VICINITY MAP - NTS





SITE MAP - NTS

CONTEXT DIAGRAM









DISTRICT BOUNDARY

HISTORIC DISTRICT

WATERFRONT

REDEVELOPMENT

Pioneer Square Preservation Board: SIGNAGE APPROVAL

HISTORIC PHOTOS



2019



ca. 1937

EXISTING PHOTOS



EXTERIOR ELEVATION - EAST



EXTERIOR ELEVATION - SOUTH




EXTERIOR ELEVATION - NORTH




EXTERIOR ELEVATION - WEST

FLOOR PLAN




Molly Moon's Homemade Ice Cream @ Washington Street Boat Landing


ELEVATIONS




PROPOSED ELEVATION - NORTH SCALE: 1/8" = 1'-0"




PROPOSED SIGNAGE DIMENSION - NORTH SCALE: 1/2" = 1'-0"









SIGN 01 S/F BEAM MOUNTED SIGN Quantity: (1)

SIGN 02 S/F BEAM MOUNTED SIGN Quantity: (1)


SIGN 03 S/F WALL MOUNTED SIGN Quantity: (1)

SIGN 04 D/F PROJECTING BLADE SIGN Quantity: (1)




Colors	Light Blue	Orange 	Black 	White
PMS	304 C	7597 C	Match building color	N/A
Translucent Vinyl	N/A	N/A	N/A	N/A
Paint	N/A	N/A	Match building color	MP 27386

SIGN 1 DETAILS




SIGN 2 DETAILS





Sign 2:


Manufacture and Install (1) Exterior Single faced illuminated open pan channel exposed neon lettering hanging sign.

- "ICE CREAM" letters to be aluminum open pan channel letter construction. Returns: 2" aluminum returns painted Orange to match PMS#7597c (satin finish). Inset letter forms to be painted White (satin finish).
- **3** Illumination to be 1/tube neon-6500 White, 12mm, 30ma. 2" glass stands.
- Mount letters to raceway. Raceway to be SignComp. Attach raceway to (2) 2" x 2" steel square tube (see detail below). Raceway, Brackets and hardware painted to match structure color Black (satin finish).
- Power to sign by others. 120 volt, 20amp circuit req.










Front View- Attachment Detail

Scale: 1 1/2"=1'-0"






Sign 3:

Manufacture and Install (1) Exterior Single faced illuminated open pan channel exposed neon lettering hanging sign.

- (A) "ICE CREAM" letters to be aluminum open pan channel letter construction. Returns: 2" aluminum returns painted Orange to match PMS#7597c (satin finish). Inset letter forms to be painted White (satin finish).
- 3 Illumination to be 1/tube neon-6500 White, 12mm, 30ma. 2" glass stands.
- Mount letters to raceway. Raceway to be SignComp. Attach raceway flush to wall with 3/8" Lag screws. Raceway and hardware painted to match structure color Black(satin finish). Seal all wall penetrations with heavy duty all weather silicone- clear.
- Power to sign by others. 120 volt, 20amp circuit req.

Full field survey required to determine or verify the most non-destructive attachment of signage to historical structure.


Internally illuminated signs shall comply with NEC article 600 and the Seattle energy code section c405 before supplying power to the sign or electrical installation.



ICE CREAM 17 7/8"

Scale: NTS

Pioneer Square Preservation Board: SIGNAGE APPROVAL



Sign 4:

Manufacture and Install (1) Exterior double faced indirect flood light illuminated aluminum panel sign.

- **A** Ice Cream Cone to be cut-out of 1/4" thick aluminum painted Black (satin finish).
- **3** Graphics to be painted White (satin finish), and Light Blue to match PMS#304c (satin finish).
- **©** Sign mounting bracket to be fabricated steel (see details left). Paint all mounting hardware to match historical structure color Black (satin finish).
- Indirect flood lighting by NSC. Power to sign by others. 120 volt, 20amp circuit req. Paint all lighting hardware and lamp shroud to match historical structure color Black (satin

Internally illuminated signs shall comply with NEC article 600 and the Seattle energy code section c405 before supplying power to the sign or electrical installation.





6 North Elevation View Scale: NTS Pioneer

Pioneer Square Preservation Board: SIGNAGE APPROVAL


EXISTING STRUCTURE CONDITIONS













PREVIOUS HISTORIC STEEL RENOVATION WORK- TO SHOW PRECEDENT FOR HOLE REPAIR AT STEEL

PERGOLA STEEL RESTORATION SCOPE OF WORK

Below is the identified restoration scope of work for the existing pergola steel structure, with subsequent figures showing examples of steel repair locations.

General Steel Structure Restoration Scope:

- 1. Remove braced frames installed for transportation; repair steel at weld locations.
- 2. Removed miscellaneous non used bolts / fasteners.
- 3. Patch all miscellaneous holes in structure (see example photo below).
- 4. Smooth raised rust patches (see example photo below).
- 5. Treat rust full extent of structure.
- 6. Fill / seal joint between existing / new corbels and columns.
- 7. Install new column base extensions per structural.
- 8. Install new grommets at new column base extensions to match existing.
- 9. Prep and paint steel structure.

Additional Restoration Scope per Column:

- A1 Cast / install new Corbel on West side of column.
- A2 See general scope.
- A3 See general scope.
- A4 Remove bolts and angles from existing removed sign, fill holes.
- A5 Remove bolts and angles from existing removed sign, fill holes.
- A6 See general scope.
- A7 See general scope.
- A8 Straighten out warped / damaged metal at column base.
- B1 Straighten out warped / damaged metal at column base.
 - Cast / install new Corbel on East side of column.
 - Cast / install new Corbel on West side of column.
- Patch existing opening behind new cast corbel.
 - Cast / install new Corbel on West side of column.
- B3 See general scope.
- B4 See general scope.
- B5 See general scope.
- B6 Remove damaged / rusted portion of existing column base. Coordinate extent with Architect.
- B7 Remove damaged / rusted portion of existing column base. Coordinate extent with Architect.
- B8 Patch existing opening behind new cast corbel.
 - Cast / install new Corbel on East side of column.
 - Reinstall non-attached existing corbel on West side of column.



Figure 1. Typ: example of holes to be patched (photo of C B1)



Figure 2: Typ. example of raised rust patches to be repaired (photo of C B2)





Figure 3: Typ. example of missing corbel (photo of C B8)



Figure 3: Typ. example of warped Column Base (photo of C B1)


RENDERINGS





RENDERINGS







RENDERINGS-PROPOSED SIGNAGE







RENDERINGS-PROPOSED SIGNAGE






RENDERINGS-PROPOSED SIGNAGE












ALLOWED



ISEATILE HARBOR-DEFARTMENT.

ICE CREAM

PROPOSED




ALLOWED






PROPOSED



ALLOWED



PROPOSED

