



Our mission, vision, and core values

Mission: deliver a high-quality transportation system for Seattle

Vision: connected people, places, and products

Committed to **5 core values** to create a city that is:


- Safe
- Interconnected
- Affordable
- Vibrant
- Innovative

For all



Presentation overview

- 1. Project goals
- 2. Project overview
- 3. Previous community outreach
- 4. 10% Design overview
 - Transit
 - Bikes
 - Pedestrians
 - Utilities
 - Parking
 - Intersections
- 5. Project schedule
- 6. What's next
- 7. Contact us





Project goals

- Faster and more frequent bus service
- Improved access to transit
- Improved safety for those walking, biking, driving, and riding the bus





Project background

- 4 mile corridor
- 235 driveways
- At least 5 foot sidewalks on both sides of the street throughout the corridor
- Bike lanes and sharrows
- Unrestricted on-street parking and no parking
- 6,300 daily bus boardings; Route 120 is one of the busiest and most productive routes in the city
- Average Daily Traffic declined about 10% since 2009





Community summary

NEIGHBORHOOD NUMBERS

		Delridge	Citywide
Renter households	%	40.7	53
People under 18 years of age	%	16.8	15
People age 65 and over	%	7.9	11
Persons of color	%	39.1	33
Language other than English spoken at home	%	22	22
High school or higher	%	90.4	93
Bachelor's degree or higher	%	42.7	57
Median household income	\$	64,258	65, 277
Unemployed	%	9.9	7
Population below poverty level		13.1	14
Source: 2009-2013 American Community Surve	٥V		

Source: 2009-2013 American Community Survey



Project overview and design features

Redesign Delridge
Way SW to balance
the needs of everyone
who use the corridor
















Adding neighborhood greenway connections

RapidRide H Line

Partnering with King County Metro to upgrade Route 120 into the RapidRide H Line by 2021


DELRIDGE - H LINE

Downtown Seattle to Delridge to Burien





Project schedule





Previous community outreach - what we've heard

Fix potholes and bad pavement

We're planning to pave between the West Seattle Bridge and Sylvan Way SW and to make minor repairs in the rest of the corridor

Make buses faster and more frequent

We're adding bus only lanes and bus signals to keep buses on time and out of traffic







Reduce speeding and create a neighborhood feel

We're adding about 2 miles of landscaped median islands and new public art





We value the bus as a neighborhood connector

We've worked with Metro to have RapidRide stations about 1/3 mile apart instead of 1/2 mile apart

We want safer and more accessible options for people biking

We've added a southbound protected bike lane and are making new connections to adjacent neighborhood greenways




Street channelization details (10% Design)

SW Andover St to SW Graham St

Key features:

- Landscaped median islands
- 24/7 bus lanes (off-peak parking removed)
- Southbound protected bike lane (parking removed)








Street channelization details (10% Design)

SW Graham St to SW Roxbury St

Key features:

- Peak bus lanes, off peak parking
- Southbound protected bike lane (parking removed)








TYPICAL EXISTING

Transit details (10% Design)

SW Andover St to SW Graham St

Key features:

- New 24/7 bus lanes (off-peak parking removed)
- 5 new RapidRide stations








Transit details (10% Design)

SW Graham St to SW Roxbury St

Key features:

- New peak bus lanes, off-peak parking
- 2 new bus queue jump signals
- 10 new RapidRide stations







Transit details (10% Design)

Proposed bus stop changes

- 28 enhanced RapidRide Stations at 14 locations
 - Maintain 23 existing Route 120 stops
 - Add 5 new stations
- Average Spacing
 - Existing, 0.22 mile
 - Proposed 0.32 mile
 - 0.1 miles is about a 2-minute walk







Transit details (10% Design)

Proposed bus stop changes

	Existing Stop Locations	Total Ridership (on + off)	Proposed Station Locations	Change from Existing
ge .	Andover St	724	Andover St	Stop remains
	Genesee St	498	Genesee St	Stop remains
	Oregon St	117		Removed
	Alaska St	85		Removed
	Edmunds St	59		Removed
	Hudson St	161	Hudson St	Stop remains
	Brandon St	455	Findlay St SW	New (NB and SB). Stops consolidated at Findlay
	Juneau St	283	rinulay St SVV	
	Graham St	119	Graham St (24th Ave)	Stop remains
Delridge	Holly St	127	22nd Ave	Move to 22nd Ave
Loop	Croft PI SW	182		Removed
	Myrtle St	284	Myrtle St	Stop remains
	Webster St / 21st St	474	21st Ave	Stop remains
	Kenyon St	199	Kenyon St	Stop remains
	Thistle St	450	Thistle St	Stop remains
	Trenton St	505	Trenton St	Stop remains
	Henderson St	38		Consolidate with Trenton St
	Barton St	44		Removed
	Cambridge St	9		Removed
	22nd Ave (Barton St)	no data		Removed
	25th Ave (Barton St)	no data	25th Ave	Stop remains
	26th Ave (Roxbury St)	no data	26th Ave	Stop remains
	20th Ave (Roxbury St)	no data		Removed
	16th/ 17th Ave (Roxbury St)	no data	16th Ave	NB stop remains, move SB stop to 16th




16

Metro Project Update

Westwood Village & White Center

- Improvement to Westwood Village hub area
- White Center hub improvements
- White Center pathway enhancements
- Non motorized access improvements




KAPIDRIDE

Metro Project Update

Burien

- Stop consolidation
- Improve connection to Downtown Seattle for Burien residents (speed and reliability)
- Non-motorized access improvements
- BAT Lanes



Current Designed Improvements

- Pedestrian safety improvements
- ADA improvements
- Larger passenger waiting areas at stations
- Priority signals for buses
- Designated bus-only lanes
- Roadway chances to promote safer vehicle speeds and better traffic flow
- Roadway pavement repairs
- Route alignment to provide better access to downtown Burien and the Burien Transit Center (BTC)
- Easier ways to transfer between buses and RapidRide lines

Phase 2 Outreach

- The outreach will help prioritize which amenities residents would most like to see at their station.
- The outreach included an open house (October 10th) and in person meetings at community centers and bus stops through mid November 2018, asking riders to prioritize the following amenities at their station:
 - Real-time arrival information
 - Seating
 - Shelter
 - Lighting

Next Phase

• Spring 2019: Present more detailed design and discuss construction impact with residents and businesses


Metro Next Steps

- Currently: Reviewing 30% design
- **Spring 2019:** Compete 60% design and continue community engagement in coordination with SDOT
- 2019: Plan for construction
- 2020: Begin construction
- 2021: H Line service begins



Next steps

- Review community feedback on 10% Design
- Develop 30% Design
- Anticipate further community outreach and engagement in Spring 2019





Contact us

CJ Holt, SDOT Project Manager

Dan Anderson, SDOT Communications and Outreach Lead

Phone: 206-684-8105

Email: DelridgeTransit@Seattle.gov

Jerry Roberson, King County Metro Project Manager Robyn Austin, King County Metro Communications raustin@kingcounty.gov

