# **Ballard Link Extension** Project updates

International Special Review District 1/14/25



# Why we're here today

- Ballard Link Extension overview
- Chinatown-International District (CID) additional studies for Ballard Link Extension



# Project overview



# **Ballard Link Extension**

- Included in Sound Transit 3 (ST3) voter approved plan.
- Adds nearly eight miles of light rail service, including a new light rail-only downtown tunnel.
- Includes nine new stations from Chinatown-International District to Ballard.



## **Ballard Link Extension (BLE)** Project timeline







# PLANNING



### 2017–2023

#### **Alternatives development**

- 2018: Early scoping
- 2019: Scoping
- 2019: Sound Transit Board identifies preferred alternatives and other alternatives

#### **Environmental review**

- $\oslash$ 
  - 2022: Publish West Seattle Ballard Link Extension (WSBLE) Draft Environmental Impact Statement (EIS)



2023: Sound Transit Board confirms or modifies preferred alternatives

### 2024–2026

#### **Environmental review**

- Fall 2024: NEPA Scoping
- 2025: Publish BLE Draft EIS
- Public comment period
- Board confirms or modifies preferred alternatives
- 2026: Publish BLE Final EIS
- Board selects project to be built
- Federal Record of Decision



### PUBLIC INVOLVEMENT

## Racial Equity Toolkit: Centering community input

- Recognize the multitude of past harms inflicted on the community from past infrastructure projects and policies that have ongoing effects today
- Strong concern over displacement of businesses in the CID, which are valued as places of gathering and community wealth-building, and potential loss of cultural identity and community ownership of land
- Desire to see additional near-term engagement between community and agency partners to collectively address remaining questions, minimize potential impacts and maximize community benefits, whether as part of design, through mitigation approaches, or as part of broader partnerships
- Support for investment in public spaces that foster connections between CID and Pioneer Square, promote safety and a sense of belonging, and support for an improved experience for riders accessing transit services







7

### **BLE Areas of Further Study Completed (2022-2023)**





## **Ballard Link Extension** *alternatives*



Other Environmental Impact Statement (EIS) alternatives



### Draft EIS Alternatives Chinatown-International District / South Downtown



#### \*Key areas identified in Board motion from March 2023 for additional study

Note: The International District/Chinatown Station 4th Avenue Shallow and 4th Avenue Shallower Alternatives would necessitate reconstruction of the existing Stadium Station.



10 Diagrams are not to scale and all measurements are approximate for illustration purposes only.



2016



# PLANNING

### 2017–2023

**Alternatives development** 

- 2018: Early scoping
- 2019: Scoping



2019: Board identifies preferred alternatives and other alternatives

#### **Environmental review**

- 2022: Publish WSBLE Draft EIS
- 2023: Board confirms or modifies preferred alternatives

### 2024–2026

#### **Environmental review**

Fall 2024: National Environmental Policy Act (NEPA) Scoping

2025: Publish BLE Draft EIS

Public comment period

Sound Transit Board confirms or modifies preferred alternatives

#### 2026: Publish BLE Final EIS

Board selects project to be built

Federal Record of Decision

### PUBLIC INVOLVEMENT



# Construction approach and duration review

# **Construction approach and duration review**

Based on community feedback and Sound Transit Board requests, the Sound Transit technical team **conducted the following activities to optimize CID alternatives**:

- Conducted extensive further studies in the fall of 2022 and early 2023, including engaging community through workshops, consultants and agency partners.
- Engaged with the independent consultant to the Sound Transit Board to review refinement ideas, particularly for the 4th Avenue Shallow alternative, and gather any additional ideas.
- Convened an independent expert panel to review the design for CID alternatives, construction approach and duration, and to offer new ideas on how to construct the 4th Ave Shallow Alternative in support of reducing construction duration and impacts.
- Refined the design and construction approach to incorporate opportunities that may reduce the construction duration and/or related impacts.





#### **Station Alternatives**

The following provides information on **construction duration drivers** and **construction activities** associated with the following CID Station alternatives:

- Dearborn Street Preferred Alternative
- 5<sup>th</sup> Avenue Shallow
  Diagonal Alternative
- 4<sup>th</sup> Avenue Shallow Alternative





### **Dearborn Street Preferred Alternative**



#### **Dearborn Street Preferred Alternative**





#### **Dearborn Street Preferred Alternative**



Ë



17 Diagrams are an approximate representation of station configuration and construction sequence based on conceptual design for illustrative purposes only.

**Ballard Link Extension** 





#### **Construction Sequence** and Methods

Stage One: Station excavation

- Major work during this stage would include:
- 1. Demolition of existing buildings
- 2. Gas line relocation (if protecting in place is determined not to be possible)
- 3. Decking to maintain traffic on Seattle Boulevard S
- 4. Station wall construction
- 5. Station excavation

This work is anticipated to take approximately three years.







### Construction Sequence and Methods

Stage Two: Tunnel Boring Machine (TBM) arrivals/departures

Major work during this stage would include:

- 1. TBM arrival at the station
- 2. TBM maintenance and re-launch of TBMs to next station

This work is anticipated to take approximately one year of intermittent activity.



**Ballard Link Extension** 





#### **Ballard Link Extension**

#### **Dearborn Street Preferred Alternative**

### Construction Sequence and Methods

#### Stage Three: Station internal structures

During this stage, station finishes would be installed, including:

- 1. Station platforms, escalators, elevators, and station entrances
- 2. Track, signal, Mechanical and electrical systems
- 3. Roadway restoration
- 4. Construction complete
- This work is anticipated to take approximately two to three years.





5th Avenue Shallow Diagonal Alternative



Ĩ

#### 5<sup>th</sup> Avenue Shallow Diagonal Alternative





### **Ballard Link Extension**

#### 5<sup>th</sup> Avenue Shallow Diagonal Alternative

Construction Duration Drivers







2

## Construction Sequence and Methods

#### Stage One: Station excavation

Major work during this stage would include:

- 1. Protection of Historic Chinatown Gate
- 2. Demolition of certain existing buildings identified within the construction area
- 3. Station wall construction
- 4. Station excavation and mining
- This work is anticipated to take approximately two years.



YEARS OF CONSTRUCTION







#### 5<sup>th</sup> Avenue Shallow Diagonal Alternative

## Construction Sequence and Methods

Stage Two: Tunnel Boring Machine (TBM) arrivals

Major work during this stage would include:

- 1. TBM arrival at the station
- 2. TBM removal and transport from site

This work is anticipated to take approximately one year of intermittent activity.







## Construction Sequence and Methods

#### Stage Three: Station internal structures

During this stage, station finishes would be installed, including:

- 1. Station platforms, escalators, elevators, and station entrances
- 2. Underground passenger connection to existing International District/Chinatown Station
- 3. Track, signal, mechanical and electrical systems
- 4. Construction complete

This work is anticipated to take approximately two to three years.





# 4<sup>th</sup> Avenue Shallow Alternative

#### 4th Avenue Shallow Alternative



28 Diagrams are an approximate representation of station configuration and construction sequence based on conceptual design for illustrative purposes only.

**Ballard Link Extension** 

Ĩ



### **Ballard Link Extension** 4th Avenue Shallow Alternative

Construction Duration Drivers

Ĩ





### **Ballard Link Extension**

#### 4th Avenue Shallow Alternative

Construction Duration Drivers

Soil Conditions







#### **4th Avenue Shallow Alternative**

Construction Duration Drivers

ð

• BNSF Railway





### Ballard Link Extension 4th Avenue Shal

#### 4th Avenue Shallow Alternative

#### Construction Duration Drivers

Ĩ

4<sup>th</sup> Avenue S
 Viaduct





#### 4th Avenue Shallow Alternative

#### Construction Duration Drivers

ð

Underground
 Structures



33 Diagrams are an approximate representation of station configuration and construction sequence based on conceptual design for illustrative purposes only.

**Ballard Link Extension** 



4th Avenue Shallow Alternative construction sequence and methods



## Construction Sequence and Methods

#### **Construction Activities**

- 3 stages spanning 10 to 12 years
- Activities include ideas moved forward from refinement process





#### 4th Avenue Shallow Alternative

### Construction Sequence and Methods

#### Stage One: I-90 to S Jackson Street, east side of 4th Avenue S

- 1. 4th Avenue S viaduct demolition
- 2. Cut-and-cover tunnel construction
- 3. New permanent 4th Avenue S structure and roadway construction

This is anticipated to take approximately two years.



36 Diagrams are an approximate representation of station configuration and construction sequence based on conceptual design for illustrative purposes only.

**Ballard Link Extension** 




#### **Construction Sequence** and Methods

Stage Two: I-90 to Jackson Street, west side of 4th Avenue S

- 1. 4th Avenue S viaduct demolition
- 2. Cut-and-cover tunnel construction
- 3. New permanent 4th Avenue S structure and roadway construction
- 4. Sewer line relocation
- 5. Station and tunnel excavation under new 4th Avenue S viaduct

### This stage is anticipated to take approximately three years.



37 Diagrams are an approximate representation of station configuration and construction sequence based on conceptual design for illustrative purposes only.





# Construction Sequence and Methods

#### Stage Three: S Jackson Street to S Main Street

- 1. Temporary decking for ICON apartment building
- 2. S Main Street bridge demolition over BNSF train tracks
- 3. 4th Avenue S viaduct demolition and S Jackson Street
- 4. Demolition of a retaining wall system adjacent to the BNSF train tracks
- 5. Cut-and-cover tunnel construction
- New permanent 4th Avenue S roadway and S Jackson Street bridge reconstruction
- 7. S Main Street bridge reconstruction over BNSF train tracks

### This is anticipated to take approximately four years.



**38** Diagrams are an approximate representation of station configuration and construction sequence based on conceptual design for illustrative purposes only.







#### **Stage Four: Station construction**

- 1. Station platforms, escalators, elevators, and station entrances
- 2. Underground passenger connection to existing International District/Chinatown Station
- 3. Track, signal, mechanical and electrical systems
- 4. Construction complete

This is anticipated to take approximately five to seven years and would overlap with Stage 3.









#### 4th Avenue Shallow Alternative

# Construction Sequence and Methods

#### Stage Four: Station construction

- Station platforms, escalators, elevators, and station entrances
- 2. Underground passenger connection to existing International District/Chinatown Station
- 3. Track, signal, mechanical and electrical systems
- 4. Construction complete

This is anticipated to take approximately five to seven years and would overlap with Stage 3.



40 Diagrams are an approximate representation of station configuration and construction sequence based on conceptual design for illustrative purposes only.



### Ballard Link Extension

#### 4th Avenue Shallower Alternative

Additional major work includes:

- Cut-and-cover tunnel construction between S Main Street and Jefferson Street
- Reconstruction of retaining wall adjacent to BNSF train tracks between S Main Street and Jefferson Street
- Yesler Way bridge reconstruction (S Main Street bridge over BNSF train tracks would not be demolished and reconstructed)

This work would occur during Stage 3 and have a similar construction duration as Stage 3 for 4th Shallow Alternative.



41 Diagrams are an approximate representation of station configuration and construction sequence based on conceptual design for illustrative purposes only.



Maximizing regional and local connections

# Maximizing regional and local connections

- Developed ridership assessment to understand difference for local and regional travel between alternatives
- Assessed differences to regional and local access trips (examined sample trips, updated trip times and assessed how trips might differ and who would experience those differences)
- Developing pedestrian and transit access improvements through
  South Downtown Hub and Ballard Link Extension planning process
- Exploring station and transfer path refinements to improve access and passenger experience
- Upcoming: Developing wayfinding and signage recommendations to improve system and station access legibility



# **CID Additional Study Results Online**

Learn more about construction approach and duration CID Station alternatives, efforts to maximize regional and local connections and accessibility, including opportunities to advance improvement projects and public transit connections through the South Downtown Hub planning process.

### ballardlink.participate.online

About NEPA scoping Alternatives 🕇 Additional studies ᠇

2022 WSBLE Draft EIS Property owners Resource library

#### Chinatown-International District (CID) Additional Study Results (2023 - 2024)

In March 2023, the Sound Transit Board adopted motion <u>M2023-18</u> which identified a preferred alternative for the Ballard Link Extension project. As part of this motion, the Board directed staff to further study ways to minimize or eliminate construction impacts to the Chinatown-International District (CID) to significantly reduce the duration and effects of construction and maximize connections to all regional and local transit modes. Materials from these additional studies are included below.

#### Construction approach and duration

- System Expansion Committee 11/14/24 presentation [English] [Traditional Chinese] [Simplified Chinese] [Vietnamese]
- CID Construction Click & Learn Activity [English] [Traditional Chinese] [Simplified Chinese] [Vietnamese]
- Report on construction approach and duration for CID Station alternatives [English] [Traditional Chinese] [Simplified Chinese] [Vietnamese]

#### Maximizing regional and local connections

- System Expansion Committee 11/14/24 presentation [English] [Traditional Chinese] [Simplified Chinese] Vietnamese]
- CID regional and local access connections video [English] [Cantonese] [Mandarin]
- Maximizing regional and local connections resource packet [English] [Traditional Chinese] [Simplified Chinese]
  Vietnamese]

Additionally, the Board directed Sound Transit staff to work with the City of Seattle and King County and in partnership with the community to explore opportunities to advance improvement projects and public transit connections through the South Downtown Hub plan. Check out the <u>South Downtown Hub Online Open House</u> to learn more.

CID additional study materials are being provided for informational purposes and as resources for the Sound Transit Board and the public in advance of Ballard Link Extension Draft EIS publication in 2025, which will be followed by a public comment period and potential Board action to confirm or modify the preferred alternative.



# **Discussion and Next Steps**



2016



# PLANNING

### 2017–2023

**Alternatives development** 

- 2018: Early scoping
- 2019: Scoping



2019: Board identifies preferred alternatives and other alternatives

### **Environmental review**

- 2022: Publish WSBLE Draft EIS
- 2023: Board confirms or modifies preferred alternatives

### 2024–2026

#### **Environmental review**

Fall 2024: National Environmental Policy Act (NEPA) Scoping

2025: Publish BLE Draft EIS

Public comment period

Sound Transit Board confirms or modifies preferred alternatives

#### 2026: Publish BLE Final EIS

Board selects project to be built

Federal Record of Decision





### Overview

- Partnership of Sound Transit, City of Seattle, King County, and community towards an implementable plan.
- Through engagement series, working on visioning and prioritization of potential investments to streets and public spaces that help connect neighborhoods and regional transit modes.
- Builds upon and scales up past community-based plans and concurrent projects and planning initiatives.









soundtransit.org

f У 🗿



# 4th Avenue Shallow alternative refinement process



### **Ballard Link Extension**

### **WSBLE Further Studies (2022-2023)**

#### **BNSF** Railway Proximity

- Construction approach modified to address BNSF concern about proximity of construction to active freight operations
- Secant walls rather than slurry walls used for construction next to BNSF
- Resulted in lengthening construction duration by one year
- Does not resolve all risks associated with construction next to BNSF









#### **Ballard Link Extension**

### Independent consultant to the Board ideas

"Top down" construction with new permanent viaduct

- Permanent rather than
  temporary deck
- Reduces duration of traffic effects by one year
- Incorporated into design as part of further studies in late 2022 and early 2023







# Multiple construction access locations

 Additional construction access location suggested by panel to reduce construction duration







## Multiple construction access locations

- Additional access location suggested at Seattle Boulevard
- Not enough space for ramp, too steep for construction equipment
- Not incorporated into design







# Multiple construction access locations

- Additional access location suggested at Main Street
- Proximity to BNSF railway, conflict with existing retaining wall, minimal available space
- Not incorporated into design









#### Full traffic closure

- Proposed full closure of 4th Avenue for up to four years
- Could reduce overall construction duration by up to three and a half years
- Would likely result in substantially greater traffic and transit detours into CID and Pioneer Square neighborhoods
- Some traffic could detour to regional transportation facilities such as I-5 and SR 99
- Not incorporated into design







### **Independent Expert Panel**

#### Pipe box

- Never been done before: Length would exceed any achieved for this construction method to date, posing substantial risk
- Could potentially avoid need to demolish 4th Avenue viaduct and reduce construction duration by four years
- Station would need to be very deep and would be an elevator-only station
- At least some of viaduct would still need to be reconstructed to accommodate vertical construction shafts

(90) Open cut Pipe box tunnel 南第五기 Potential secondary vent/egress shaft under viaduct 4th Ave TBM retrieval pit Station access shaft

• Not incorporated into design





# Summary

- The Dearborn Street Preferred Alternative is expected to take about 6-7 years to construct, with a limited number of construction duration drivers (gas line, Seattle Blvd and 6<sup>th</sup> Avenue)
- The **5th Avenue Shallow Diagonal Alternative** is expected to take about **5-6 years to construct** with construction duration drivers including prioritizing minimizing business displacements, minimizing effects to historic buildings and avoiding effects to the Historic Chinatown Gate
- The 4th Avenue Shallow and Shallower Alternatives are expected to take 10-12 years to construct with construction drivers including very limited construction access, proximity to BNSF Railway, poor soil conditions, complex underground structures, and more
  - > Independent experts were consulted to develop ideas to further reduce duration and impacts
  - Ideas were reviewed and incorporated where shown to reduce duration and community impacts (ideas incorporated into the Draft EIS design do not ultimately reduce the construction duration overall)
  - One idea, full closure of 4<sup>th</sup> Avenue South, may reduce construction duration by up to 3.5 years, but would result in increased community impact with substantially greater traffic detours locally and regionally
  - Refinement ideas do not address construction duration risk related to proximity to BNSF



# Cost drivers and risk: 4th Avenue Shallow

- **Construction duration risk:** 
  - Risk of increase to construction duration (beyond 10 to 12 years) due to stringent safety requirements and other restrictions with construction next to active BNSF Railway mainline tracks; delays could affect the entire BLE project schedule
- Scope growth:
  - Additional scope to rebuild 4<sup>th</sup> Avenue viaduct
- Construction complexity:
  - Construction next to and over the **active BNSF Railway mainline tracks**
  - Complex construction sequencing due to lack of construction staging access while maintaining traffic and pedestrian access on 4<sup>th</sup> Avenue S in this constrained area
  - Maintaining traffic and neighborhood access during construction
- Market conditions:
  - Risk profile of the job will limit competition and increase the markup
  - Bridge structure construction experience over a tunnel station and tunneling construction experience may affect competition



Maximizing regional and local connections

# Maximizing regional and local connections

- Developed ridership assessment to understand difference for local and regional travel between alternatives
- Assessed differences to regional and local access trips (examined sample trips, updated trip times and assessed how trips might differ and who would experience those differences)
- Developing pedestrian and transit access improvements through
  South Downtown Hub and Ballard Link Extension planning process
- Exploring station and transfer path refinements to improve access and passenger experience
- Upcoming: Developing wayfinding and signage recommendations to improve system and station access legibility



# **Ridership Modeling Background**

- Ridership modeling provides **potential scale and magnitude** of system and station usage
- High volume of transit choices in the Seattle core makes modeling results highly sensitive to small changes, such as station access times
- Modeling does not predict individual behavior (e.g., people choose the travel choice that makes sense for them based on many different factors)



Example transit network in Ridership Model



### **Ridership modeling results: 2046** Overall Link boardings between Westlake and SODO

Similar between alternatives







#### 

### **Ridership modeling results: 2046** Neighborhood boardings for CID and Midtown Stations

Similar between alternatives, with moderately higher boardings for 4th and 5th Avenue options

*(likely due to a shift in where boardings occur in central business district)* 





# **Regional and Local Travel Times**

	Dearborn Street (Preferred)	4th Ave Shallow*	5th Ave Shallow (Diagonal)		
Travel time between regional destinations (minutes):					
Hing Hay Park to SeaTac Airport	45	44	43		
CID Library to SeaTac Airport	47	53	52		
Danny Woo Garden to SeaTac Airport	52	48	47		
Occidental Square to SeaTac Airport	50	52	53		
Bellevue Transit Center to SeaTac Airport**	70	65	66		
Kent (Sounder) to South Lake Union	57	55	59		
SeaTac Airport to Harborview Medical Center	54	54***	54***		
SeaTac Airport to Swedish Hospital	63	59***	59***		

\* Assumes 4th Avenue Shallow configuration in CID. Shallower configuration would save approximately one minute.

\*\* Riders could also take STRIDE BRT from Bellevue Transit Center to SeaTac Airport in 44-49 minutes.

\*\*\* Instead of walking or taking a King County Metro bus from Midtown Station, riders could also get off at the future station serving CID and take the Seattle Streetcar to Harborview Medical Center (68-69 minutes total) or Swedish Hospital (70-72 minutes total)



#### Walk time to nearest 1-Line station\*:

0-5 min 6-10 min 11+ min

	Dearborn Street (Preferred)	4th Ave Shallow	5th Ave Shallow (Diagonal)
Hing Hay Park	4 min	3 min	2 min
Little Saigon	15 min	13 min	12 min
Yesler Terrace	9 min	13 min	12 min
Occidental Square	6 min	8 min	9 min
Lumen Field	6 min	4 min	7 min
T-Mobile Park	10 min	11 min	14 min
Central Library	7 min	2 min	2 min
Seattle City Hall	2 min	2 min	2 min
Harborview	8 min	9 min	9 min
Virginia Mason	13 min	8 min	8 min
Frye Art Museum	9 min	8 min	8 min
Sounder Station	6 min	2 min	4 min
Amtrak Station	7 min	2 min	5 min
Colman Dock	10 min	8 min	8 min



### Access in Stations CID Dearborn Street Station



Based on conceptual level of design, subject to change.

### **Access in Stations**

### Midtown James Street Station (James Tunnel)



### **Access in Stations**

### Midtown James Street Station (Jefferson Tunnel)



### Access in Stations CID 5th Avenue Shallow Diagonal



### Access in Stations CID 4th Avenue Shallow

