## **Section 4**

### **Conservation Measures**

Conservation measures are BMPs used to ensure that activities avoid and minimize impacts to ESA-listed species and their habitat. This section describes 8 general categories of conservation measures that apply to each of the 14 construction methods covered by the Seattle Biological Evaluation and described in Section 3:

- 1. Approved work windows for ESA-listed species
- 2. Stormwater pollution prevention
- 3. Work area isolation
- 4. Fish handling
- 5. Overwater structure size
- 6. Piling installation and noise abatement
- 7. Shoreline and aquatic habitat protection
- 8. Pesticides.

The conservation measures described here were identified for each method in the preceding section. Each measure is numbered sequentially across the 8 general categories. There are a total of 75 conservation measures covered in this Seattle Biological Evaluation.

City of Seattle project managers and other applicable lead staff will indicate on an automated **Specific Project Information Form** (SPIF) those conservation measures that will be applied to a specific activity or suite of activities. There may be additional conservation measures other than those presented here. If additional conservation measures or BMPs will be used, the project manager or lead staff must identify and describe those activities on the SPIF. See the City of Seattle Facilitated Permitting website for the SPIF.

http://www.seattle.gov/util/Engineering/Consulting Resources/Permit Coordination/index.asp

The SPIF is also presented in Appendix A of this document.

# 4.1 Approved Work Windows

All work shall comply with the approved work windows/timing restrictions for the protection of ESA-listed species or the species they forage upon in the Seattle action areas. These windows can overlap for various species and locations.

### A. Fish Windows

**Freshwater Fish Window.** Follow the approved freshwater work window for ESA-listed species in the Seattle action areas (Table 4-1).

Table 4-1
Approved freshwater work windows for ESA-listed fish species in the Seattle action areas\*

Waterbody	Location	Window
Lake Washington Ship Canal	Upstream of Locks to east end of Montlake Cut	Oct 1 – Apr 15
Lake Washington south of I-90	>1 mile from Kelsey Creek or Cedar River	Jul 16 - Dec 31
	Within 1 mile of Kelsey Creek or Cedar River	Jul 16 – Jul 31 Nov 16 – Dec 31
Lake Washington	Between I-90 and SR 520	Jul 16 – Apr 30
Lake Washington north of SR 520	Between SR 520 and line due west from Arrowhead Point	Jul 16 – Dec 31
	North of line due west from Arrowhead Point	Jul 16 – Jul 31 Nov 16 – Dec 31
Tributaries to Lake Washington in Seattle		Jul 1 – Aug 31
Duwamish River, its tributaries and tributaries to Puget Sound		Jul 1 – Sep 30
Source: Corps et al. 2007	1	

<sup>\*</sup>Work window for a stream applies to all its tributaries, unless otherwise indicated

**Marine Fish Window.** Follow the approved marine and estuarine work window for ESA-listed fish species (Coastal-Puget Sound bull trout, Puget Sound Chinook salmon, and steelhead) and forage fish in the Seattle action areas. (see Figure 1).

- Have City crew or contractor make use of tide tables to select the lowest tides for work.
- Where a river, stream, or tributary enters marine or estuarine water, work windows listed in Table 4-2 apply to all tidally influenced portions of a river, stream or tributary.
- If forage fish spawning habitat is documented in the project area, then the work window for that species applies. For the Seattle Biological Evaluation, 'forage fish' means surf smelt, Pacific sand lance, and Pacific herring. Chinook salmon are forage fish for bull trout as are other small salmonids.
- To determine whether your project lies within documented forage fish spawning habitat, refer to the surf smelt, Pacific sand lance, and Pacific herring maps provided by WDFW <a href="http://wdfw.wa.gov/fish/forage/forage.htm">http://wdfw.wa.gov/fish/forage/forage.htm</a>.

Table 4-2
Approved marine/estuarine work windows for Puget Sound Chinook salmon, bull trout, steelhead and forage fish in Seattle action areas\*

Species	Location	Window
Salmon (Puget Sound Chinook)		Jul 2 – Mar 2
Bull trout (Coastal-Puget Sound bull trout)		July 16 – Feb 15
	Duwamish Waterway mouth to upper turning basin (SE ¼ of NW ¼ section 4, T23N, R4E)	Oct 1 – Feb 15
Steelhead*		
Forage fish:		
Surf smelt		Apr 1 – Aug 31
Pacific herring		May 1 – Jan 14
Pacific sand lance		Mar 2 – Oct 14
Source: Corps 2001		

<sup>\*</sup>Steelhead are pending listing under the ESA. If listed, steelhead timing windows will follow the timing windows for salmon.

**Several Work Windows**. If several work windows for species apply for a specific project, work windows must be combined, including the work windows for bald eagles.

For example, if the project is in north Puget Sound, Pacific sand lance spawning habitat is present and work windows would be:

Salmon July 2 – March 2
Bull trout July 16 – February 15
Pacific sand lance March 2 – October 14

Taking the days that the approved work windows have in common, the time the project could be constructed is **July 16 – October 14**.

### B. Bald Eagle Window

**Follow approved work window for bald eagles.** Determine the distance from the nearest point of the project to the location of documented bald eagle nests, roosts and foraging habitat (Table 4-3).

Table 4-3
Approved work windows and activity distances for bald eagles in the Seattle action areas<sup>1</sup>

Location/Activity	Distance from location	Window
In line of sight	> 0.5 mile (800 m)	Wintering period <sup>2</sup>
		Apr 1 – Oct 30
		Nesting period
		Aug 16 – Dec 31
Out of line of sight	> 0.25 mile (400 m)	Same as above
Pile driving	< 0.5 mile (800 m)	Aug 16 – Dec 31
Vibratory pile driver only	0.5 mile to 1 mile (800 m -1.6 km)	Jan 1 – Aug 15
Source: USDI 1986		

<sup>&</sup>lt;sup>1</sup>Data are U.S. Fish and Wildlife Service regulations. The bald eagle is under delisting consideration in 2007.

<sup>&</sup>lt;sup>2</sup>Work is scheduled outside of the wintering period (October 31 through March 31) and/or the nesting period (January 1 through August 15) or **is restricted to a very short period of time to minimize disturbance**. 'Important wintering areas' are defined as documented communal roost sites and concentration areas of waterfowl and/or fish that attract large numbers of bald eagles. Screening activities from view (with vegetation or topography) or maintaining 0.5 mile (800 m) distance can minimize potential disturbance.

### Follow general conservation measures:

- If habitat removal is proposed, the quantity of habitat removed is limited to a very small amount (therefore insignificant and discountable).
- Noise and activity levels of a proposed activity are kept within ambient levels already present at a site. If bald eagles at a site are tolerant of levels of existing activities, disturbance may be insignificant.

### 4.2 Stormwater Pollution Prevention

### A. Develop Temporary Erosion and Sediment Control Plan

Each project shall have onsite a written a Temporary Erosion and Sedimentation Control (TESC) plan that includes all information needed to reduce erosion and sedimentation on the project (Std Spec 1.07.15, 8-01). All projects will require the contractor/City crew to assign an onsite Erosion Control Lead to oversee the work and ensure compliance with the TESC plan (Std Spec 1-05.13[3]).

### B. Ensure Contractor/City Crew has SPCP

- The City crew/contractor shall have onsite a written Spill Prevention and Control Plan (SPCP) that describes materials to be used and measures to prevent or reduce impacts from potential spills (fuel, hydraulic fluid, etc.) (Std Spec 1-07.5[5]).
- **4.** Maintain a spill kit onsite to respond to accidental spills during construction. Ensure that spill kit is stocked with adequate containment material and other supplies to suit the specific job site and potential containment distances.

### C. Minimize Site-Preparation-Related Impacts

- **5.** Confine construction impacts to the minimum area necessary to complete the project and delineate impact areas on project plans. Flag boundaries of clearing limits associated with site access, construction, and staging areas as well as wetland and riparian corridor where work has been authorized.
- **6.** Establish staging and site access areas along existing roadways or other disturbed areas to minimize erosion into or contamination of sensitive areas or their buffers. Confine work to the area noted using flagging or other barriers.
- **7.** Limit clearing and grubbing area to minimum required. Retain vegetation to maximum extent possible. Minimize clearing and grubbing effects by cutting

vegetative stems but not removing the root systems, which help to reduce erosion potential and allow native plants to regenerate.

- **8.** Divert run-off from entering the project (disturbed) area.
- **9.** Ensure proper BMPs, such as covering, berming, matting, seeding, or mulching, are implemented to prevent erosion of any excavated material.
- **10.** Stockpile large wood, trees, riparian vegetation, other vegetation, sand, and topsoil removed for establishment of staging area and reuse for site restoration.
- **11.** Salvaged debris such as roots and stumps may be used for habitat. Disposal of debris may include chipping, shredding, or grinding for reintroduction to the site as mulch (Std Specs 1-05.13(3), 1-07.5, 2-01.2, 2-10.3(2) and 8-01).
- 12. Place sediment barriers (e.g., silt fences, coir logs, wood straw, or other effective erosion control method) around disturbed sites to prevent erosion from sediment deposition from entering a waterbody.
- **13.** Keep a supply of erosion control materials (e.g., silt fence or mulch) on hand to respond to sediment emergencies. For wetland areas with high likelihood of germination, use wood straw.
- **14.** Use curb inlet sediment traps and geotextile filters, along with silt fencing, to capture sediment before it leaves the site.

### D. Avoid Heavy Equipment Fuel/Oil Leakage

- **15.** Equipment used for work below the OHW¹ or MHHW² or in riparian zones or shoreline areas shall be cleaned of accumulated grease, oil, mud, etc, and leaks repaired before arriving at the project.
- **16.** Equipment shall be fueled and serviced in an established staging area. Thereafter, all equipment shall be inspected daily for leaks or accumulation of grease, and any identified problems fixed before equipment enters areas typically covered with water.

<sup>&</sup>lt;sup>1</sup>Ordinary high water (OHW): A non-tidal (freshwater) The visible line on a bank where the presence and action of waters are so common as to leave a mark on soil or vegetation.

<sup>&</sup>lt;sup>2</sup>Mean higher high water (MHHW): A tidal (marine water) datum that is the average high water height.

- 17. Two oil absorbing floating booms appropriate for the size of the work shall be available onsite during all phases of work whenever heavy equipment is used below the OHW or MHHW. The booms shall be placed in a location that facilitates an immediate response to potential petroleum leakage.
- **18.** Vegetable-based hydraulic fluid should be substituted when machines will operate in sensitive areas or their buffer for more than incidental work.

### E. Minimize Earthmoving-Related Erosion

- **19.** Operate machinery from existing roads and paved areas where they exist in proximity to the site. In many cases, wood chippings and timber mats can provide a temporary surface where heavy equipment can access a work site.
- **20.** Use temporary materials such as geotextile barriers, hog fuel or wood pellets to stabilize haul and access routes, staging areas and stockpile areas.
- **21** Stockpile native streambed or substrate materials above the OHW for later use in project restoration. To prevent contamination from fine soils, these materials shall be kept separate from other stockpiled material not native to streambed or substrate.
- **22.** <u>If equipment wash areas are required</u>, they shall be located where washwater, sediment, and pollutants cannot enter waterbodies, including wetlands.
- **23.** No sediment shall be tracked onto paved streets or roadways. Sediment shall be removed from trucks and equipment before leaving the site.
- **24.** Remove equipment and excess supplies, clean work storage areas, and remove temporary erosion control materials and temporary fill after construction and when soils have stabilized (Std Spec 1-04.11).

### F. Minimize Stream Crossing Sedimentation

- **25.** Minimize stream and riparian crossings. <u>If possible</u>, cross at right angles to the main channel.
- **26.** Where temporary stream crossings are essential, crossings shall be managed to minimize the risk of creating erosion.

### G. General Restoration in Open Waters

**27.** For in-water work at or below OHW or MHHW, appropriate and effective erosion or other water quality control devices will be in place before project work

- begins. Control devices include sealed sand or gravel bags, silt curtains, silt fencing, or other containment systems. Deploy and maintain curtain at sufficient depth to reach bottom and contain sediment.
- 28. If mechanized equipment is used within the OHW or MHHW, only an extension arm with bucket or similar attachment shall enter the water. Conduct debris removal and work below OHW or MHHW during low water levels (fresh waters) or at low tide (marine waters). This prevents material from entering the water during construction. All debris removed shall be disposed of offsite in an approved upland disposal area.
- **29.** Confine use of equipment operating below OHW or MHHW to designated access corridors.
- I. Temporary Dewatering Plan Requirements
- **30.** Develop a Temporary Dewatering Plan (TDP) for any dewatering lasting **more than 1 day** or requiring the installation of **a trench safety system**. The City crew/contractor shall submit the TDP to the City project manager. The TDP shall contain the following minimum information:
  - · Contact information for preparer and implementation of TDP
  - · Location of point of discharge and construction schedule
  - Existing site conditions and proposed construction activities
  - · Water quantity (if applicable) and discharge volume monitoring plan
  - Impacts of temporary dewatering activities to adjacent public places or streams, wetlands, or their buffers.
  - Dewatering Suspension Plan to secure site if both water quality and quantity requirements are not met. The plan requires the City/contractor to focus efforts on TESC and dewatering treatment for the site. For sites discharging subsurface flows, the City shall require that site operations cease under the plan. All discharges from dewatering treatment systems must meet Washington state water quality requirements. If temporarily dewatering dredged material, the returned water should be cleaned to the level acceptable by regulation.
  - Emergency termination of dewatering discharges if any of the water quality and/or quantity treatment requirements are not being met.
     Routing flows to the sewer system is a last-resort option that must receive Seattle Public Utilities and King County consent prior to instigation. All reasonable treatment options (as determined by Seattle Public Utilities) must be exhausted before this is allowed.

• Other information deemed necessary to temporary dewatering activities during the review of the TDP and/or during construction.

### 4.3 Work Area Isolation

**31.** Follow proper work area isolation measures (Table 4-4)

## Table 4-4 Work area isolation

#### Measure

- 1 Determine if a cofferdam or other waterproof barrier is necessary and install it in the dry, if possible.
- 2 If water infiltrates into the work site, either through the barrier or groundwater, and must be removed, pump it to a tank or other method of treatment so that it meets water quality standards before introducing it back into the waterbody.
- 3 Where work will occur completely within the water or where isolating the work area is not practical, install a silt curtain or similar measure to minimize environmental impacts to the surrounding area.
- 4 Do not remove deployed silt curtains until turbidity within the work area has returned to background levels.
- The temporary bypass system must consist of non-erosive techniques, such as a pipe or a plastic-lined channel, both of which must be sized large enough to accommodate the predicted flow rates during construction. For projects that last longer than 1 day, a contingency plan must be developed to address unexpected storm flows. If storm flows occur and the diversion is overtopped, equipment shall be removed and the project stopped. After the flows return to normal, fish bypass and removal shall occur again to remove any fish that entered the construction area during the storm event.
- 6 Dissipate flow at the outfall of the bypass system to diffuse erosive energy of the flow. Size the dissipater for the volume and velocity of the bypassed flow. Place the outflow in an area that minimizes or prevents damage to riparian vegetation.
- 7 Except for gravity diversions that have gradual and small outfall drops directly into water, all water intake structures must have a fish screen installed, operated, and maintained in accordance with the NMFS Juvenile Fish Screen Criteria and the NMFS Addendum NMFS Pump Intake Screen Guidelines. If the diversion inlet is a gravity diversion and is not screened to allow for downstream passage of fish, place diversion outlet in a location that facilitates gradual and safe reentry of fish into the stream channel (Std Spec 2-10.3[8])
- 8 All stream diversion devices, equipment, pipe, and conduits will be removed and disturbed soil will be restored after the diversion is no longer needed.

# 4.4 Fish Handling

**32.** Follow proper fish capture and handling measures (Tables 4-5 through 4-7).

Table 4-5 Fish capture and handling general procedures

	Measure
1	Fish capture operations will be conducted by a trained, individual experienced in this type of work. Key staff working with fish removal must have the necessary knowledge, skills, and abilities to ensure the safe handling of all aquatic species.
2	The applicant must obtain any other federal, state and local permits and authorizations necessary for the conduct of fish capture activities.
3	Before conducting activities that may involve fish handling, individuals shall ensure that hands are free of sunscreen, lotion, or insect repellent.
4	Fish will be handled with extreme care and kept in water to the extent possible during transfer procedures based on Tables 4-6 and 4-7.
5	If water remains within the work area and fish are potentially present after isolation of the work area and stream diversion, electrofish, seine, and dip net the work area until catch rates reach zero fish for 3 consecutive passes.

Table 4-6 Fish capture methods

Method Required or Details			
wethod	optional	r Details	
Minnow traps	Optional	Fraps may be left in place overnight and may be used in conjunction with seining. This method has limited success in areas of flowing water (most streams), but may be beneficial in calm waters.	
Seining	Required	Use seine with mesh of such a size to ensure entrapment of residing fish age classes. This method is difficult (if not impractical) in streams with mat obstacles (wood, rock or undercut banks and insufficient area to beach not collect fish).	ny
Dip nets	Required	Use in conjunction with other methods as area is dewatered.	_
Electrofishing	Required	Use electrofishing in addition to other means of fish capture to ensure the effective capture of fish. Applicants shall adhere to NMFS Backpack Electrofishing Guidelines or SPU-approved fish elctroshocking methods.	
		If fish are observed spawning during the in-water work period (a condition likely to occur only in an emergency situation because permitted work/timing windows do not allow this), electrofishing shall not contact spawning adult fish or active redds.	
		NFMS Backpack Electrofishing Guidelines  1. Only Direct Current (DC) or Pulsed Direct Current (PDC) shall be use	ed.
		2. For conductivity <100 $\mu\Omega$ /cm, use voltage ranges from 900 to 1100. For conductivity from 100 to 300 $\mu\Omega$ /cm, use voltage ranges from 500 to 800. For conductivity greater than 300 $\mu\Omega$ /cm, use voltage to 400.	-or
		<ol> <li>Begin electrofishing with minimum pulse width. Gradually increase to the point where fish are immobilized and captured.</li> </ol>	
		<ol> <li>Do not allow fish to come into contact with anode. Do not electrofish a area for an extended period of time. Upon capture, remove fish immediately from water.</li> </ol>	an
		<ol><li>Dark bands on the fish indicate injury, suggesting a reduction in volta and longer recovery time.</li></ol>	ge
		SPU Backpack Electrofishing Guidelines Using Smith Root Backpac Electroshocker	k
		1. Program the unit for automatic setup (instructions are with unit).	
		2. Find an unobstructed section of water where fish can be observed.	
		3. Herd any fish out of the area before initiating automatic setup.	
		<ul> <li>Initiate automatic setup. Within Seattle urban creeks initial settings of fall within the following ranges:</li> <li>Hertz = 30</li> <li>Duty Cycle = &gt; 10 but &lt; 15</li> <li>Volts = &gt; 180 but &lt; 210</li> </ul>	ten
		<ol> <li>Before initiating first sweep, drop duty cycle by 2 units and voltage by 30V. Lowering these units will ensure larger fish (which conduct more voltage) will not be harmed.</li> </ol>	
		<ol><li>Conduct the first sweep at this level to remove larger fish. Smaller fish will not react at this voltage. But it may herd them from the area.</li></ol>	h
		7. On the second sweep reset to the original units from the automatic setup. This should now begin to bring in the smaller fish. If smaller fis are still avoiding the electroshocking device, increase voltage in 10-u increments until they are drawn in to the electrode. Under normal urb creek conditions in Seattle voltage should be effective below 250V.	nit

# Table 4-7 Fish handling methods

#### Method

- In areas where ESA-listed fish have been recorded, it is recommended that the transfer of fish be conducted using a sanctuary net that holds water during transfer to prevent the added stress of an out-of-water transfer.
- If using MS 222 to anesthetize fish, use the minimal amount required. Only anesthetize a few fish at a time to minimize the time fish are in MS 222 solution. Anesthetized fish must be fully recovered before being released into a stream.
- 3 Release captured fish as soon as possible.
- 4 If fish are held, provide a healthy environment for the stressed fish and minimize the holding time. Water-to-water transfers, the use of dark-shaded containers, and supplemental oxygen should all be considered in designing fish handling operations.
- 5 Provide a healthy environment for the stressed fish by using large buckets (5-gallon minimum) to prevent overcrowding and minimal handling of fish.
- 6 Place large fish in buckets separate from smaller prey-sized fish.
- 7 Monitor water temperature in buckets and well-being of captured fish.
- After fish have recovered, it is recommended they be released upstream from the project area in suitable habitat, such as a pool or area that provides cover and flow refuge. Because this action is site specific, apply these principles. Release fish:
  - As close to point of capture as possible
  - Based on the life-history stage. Juvenile fish are released downstream
    of the site to aid migration out of the system. Adult fish are released
    upstream to aid migration to spawning or resting locations.
  - Into best available habitat to reduce or decrease predation and aid recovery. Or release where good habitat exists and fish can reoccupy the work area after the project is completed.
  - At multiple release points. If a large number of fish are caught, release fish at different areas so that fish are not concentrated at one location.

### 4.5 Overwater Structure Size

### A. Floats, Docks, or Piers

**33.** Overwater structures such as piers and floats should be no larger (length and width) than needed for the specified function (Table 4-8). Minimize/reduce pier and overall footprint of structure to reduce shading impacts. In the SPIF, give rationale for project-specific pier and float size requirements.

Table 4-8

Typical Seattle Parks and Recreation marine structure size

Structure	Size	
Swim docks	20-by-40 ft to 32-by-40 ft	
Small craft floats	maximum 70 ft long	
	16 to 20 ft wide for stability	
Boat launch floats	maximum 8 ft wide for stability	
	(Must accommodate 20 users at a time)	

- **34.** Minimize/reduce piling number and space piling further apart where possible to reduce shading impacts.
- **35.** To reduce shading impacts, grating shall be installed on fixed structure surfaces during replacement to provide light transmission to the maximum extent practicable and American Disabilities Act (ADA) requirements. If grating cannot be installed in pier/float decking, consider using transparent glass blocks, prisms, or floors to obtain more light under pier.
- **36.** Flotation for floats will be fully contained in a durable protective casing to prevent breakup of the flotation material and its release into the waterway.
- 37. In marine waters, replacement floats shall be at least 4 feet above marine vegetation (e.g., eelgrass) to avoid creating new shade over marine vegetation
- **38.** Place new and replacement piers at least 2 feet above OHW or MHHW.

### B. Floating Breakwaters

**39.** Limit overall size, length and width to minimum necessary for wave attenuation and safe public use/navigation.

- **40.** Logs shall be clean and without bark.
- C. Anchoring Buoys, Floats and Floating Breakwaters
- **41** Ensure that anchor lines do not drag on the substrate or in aquatic vegetation during low water levels. Buoy cables or chains will be kept off of the bottom by the addition of a second float below the surface at the appropriate length and size to perform during all tidal and wind conditions.
- **42.** Use mechanical anchors (e.g., helical screw) in lieu of concrete anchors unless substrate (e.g., bedrock) prevents installation of screw anchors.

# 4.6 Piling Installation and Noise Abatement

- A. Piling Installation
- **43.** Plastic, cement or timber piling is preferred over steel piling.
- **44.** Use a containment boom for sawdust and debris work. <u>If in marine water</u>, a containment boom may rest on substrate rather than float at all times due to tidal action. Remove contained debris to prevent it from entering the waterway at construction completion.
- 45. If treated piling is fully extracted or cut below the mudline, cap the holes or piling with appropriate materials (e.g., clean sand or steel pile caps for cut piling). This practice ensures that chemicals from existing piling do not leach into the adjacent sediments or water column.
- **46.** Do **not** use piling treated with creosote or pentachloraphenol.
- **47.** Do **not** use hydraulic water jets to remove or place piling.
- **48.** Replace piling in same general location. Do **not** extend beyond footprint of existing structure.
- B. Piling Installation Noise Abatement
- **49.** Use a vibratory driver to the extent possible for setting piling. Geotechnical engineering can determine if this will be sufficient based on the piling material and load capacity.

- **50.** A bubble curtain or other noise attenuation method (e.g., wood blocks, nylon blocks, etc.) shall be used during impact installation or proofing of steel piling. For piling with a 10-inch or smaller diameter, the sound attenuation device must include <u>one</u> of the methods listed above. For piling with a diameter greater than 10 inches the sound attenuation device must include both the placement of a sound block between the hammer and the piling during pile driving <u>and</u> use of a bubble curtain.
- **51.** Hydroacoustic monitoring shall be used for driving large (>12-inch-diameter) steel piling.
- **52.** All reasonable measures shall be taken for the suppression of noise resulting from the work operations. All work shall be performed consistent with the applicable noise control levels set forth in SMC Chapter 25.08 and comply with Std Spec 1-07.5(4) Noise Pollution.
- Projects using an impact hammer to drive or proof steel piling in marine/ estuarine waters must deploy sound attenuation <u>and</u> have an observer onsite during all pile driving and proofing to scan open water within a certain radius around the work area (Table 4-9). Should a marine mammal (e.g., killer whales, Steller sea lions, otters) be observed within this radius, then the observer must immediately notify the pile driver operator and the operator must cease all pile driving and proofing activities immediately and only resume pile driving or proofing when all marine mammals have left the radius around the work area.

Table 4-9 Impact pile driving/proofing steel piling distances in marine/estuarine waters with observable marine mammals\*

Steel piling size	Radius around work area
12-inch diameter or less	75 ft
13 to 16-inch diameter	200 ft
17 to 24-inch diameter	1120 ft

#### \*Based on the Practical Spreading Loss model:

160 dB<sub>rms</sub> disturbance threshold for marine mammals (WSDOT 2006)

187 dB<sub>rms</sub> at 9m for impact driving 16" steel piling (WSDOT 2006)

<sup>180</sup> dB<sub>rms</sub> at 10m for impact driving 12" steel piling (Hastings and Popper 2005)

<sup>208</sup> dB<sub>peak</sub> at 10m (assume 198 dB<sub>rms</sub>) for impact driving 20" steel piling (Illingsworth & Rodkin 2001)

<sup>198</sup> dB<sub>rms</sub> at 10m for impact driving 24" steel piling (Hastings and Popper 2005)

<sup>15</sup> dB<sub>rms</sub> reduction in sound with bubble curtain (WSDOT 2006)

# 4.7 Shoreline and Aquatic Habitat Protection

### A. All Projects/All Structures

- **54.** Perform the work in the dry whenever possible (80-90% of the time).
- **55.** Minimize construction impacts by conducting work during minus tides or low water levels.
- **56.** All fill materials will be of clean, washed, and commercially-obtained material.
- **57.** To avoid entraining fish, an excavated trench exposed to open water between tidal cycles should be sloped or filled with sand and gravel to optimize fish habitat.
- **58.** Equipment and materials are mobilized to and from the site via upland access or construction barge. <u>If the project area is not isolated and dewatered</u>, a silt curtain will be installed.
- **59.** <u>If a construction barge is used</u>, it shall not ground or rest on the substrate at anytime or anchor over vegetated shallows.
- **60.** Take care to prevent spread of invasive plant species during their removal.
- **61** Plant the project shoreline with native riparian vegetation. City crew/contractor will ensure 80% survival of the planted material at 1, 3, and 5 years after installation. Riparian planting plans will be submitted along with the project permit application.
- **62.** Require City crew/contractor to retrieve any debris generated during construction that has entered the water and sunk to dispose of it at an upland facility.

#### B. Beach Nourishment/Substrate Addition

- **63** Beach material will typically be washed gravel whenever possible to minimize the amount of fill eroding into the waterbody. Sands may be applied above the OHW or MHHW depending on the project purpose.
- **64.** Use clean gravel (less than 3% fines by weight [material passing a number 200 sieve per U.S. standard sieve size]) to avoid turbidity during gravel placement.

#### C. Boat Launch

- 65. Place appropriate habitat gravel mix as needed. The mix shall meet WDFW Hydraulic Permit Application requirements.
- **66.** No wet concrete or epoxy shall be placed in the wetted perimeter. Concrete and epoxy must be cured before they come into contact with the water.

### D. Bulkhead Repair/Replacement

- **67.** Move the bulkhead as far back as possible above the OHW or MHHW.
- **68** Construct bulkhead to contain habitat complexity, such as coves, where recreational use allows.
- **69.** Plant new bulkhead with native riparian vegetation where not in direct conflict with recreational use.

### E. Riprap Addition

- **70.** When installing riprap, include rootwads and/or large woody debris to increase habitat complexity.
- 71 Cover all newly placed riprap with habitat mix to fill voids and cover the rock to benefit benthic organisms. In locations where habitat mix will wash away rapidly, it may be deemed unnecessary to install.

### 4.8 Pesticides

- **72.** Pesticides will be applied only under direct supervision (within line of sight) of a licensed applicator.
- **73.** When native plants are being restored to a project site, pesticides can be used to control those weeds listed in the King County Noxious Weed List. Plants that are highly invasive and damaging to native riparian habitats include Himalayan blackberry, clematis, morning glory, and Japanese knotweed.
- **74.** Within the shoreline and riparian zone of all waterbodies, use only herbicide products containing glyphosate for general weed control and/or selected Washington State Department of Ecology-approved herbicides mandated for aquatic noxious weed control.

**75.** Other chemicals, such as foaming agents used to kill roots growing into utility pipes, will be subject to Tier 1 chemical applications exemptions that will require approval from the Seattle Parks and Recreation IPM coordinator and the Office of Sustainability and Environment.